

## **TECHNICAL APPENDIX 13.5: CONSTRUCTION NOISE ASSESSMENT OF INVERGARRY TEE OHL DISMANTLING**

- 1. TECHNICAL APPENDIX 13.5: CONSTRUCTION NOISE OF INVERGARRY  
TEE OHL DISMANTLING 1-2**

## 1. TECHNICAL APPENDIX 13.5: CONSTRUCTION NOISE OF INVERGARRY TEE OHL DISMANTLING

Table 1-1: BS 5228-1 Assessment – Access and Removal – Evenings and Weekends

NSR	Shortest distance to felling buffer boundary (m)	Daytime Construction Noise Limit (dB)	Total Equivalent Noise Level at 10 m from OHL (dB)	Sound Pressure Level at Receptor (dB)	Construction Noise Limit Exceedance
1	3214	55	81	42	-13
2	1649	55	81	42	-13
3	6695	55	81	30	-25
4	6704	55	81	30	-25
5	6705	55	81	30	-25
6	6590	55	81	45	-10
7	6890	55	81	37	-18
8	7259	55	81	36	-19
9	7291	55	81	36	-19
10	7379	55	81	37	-18
11	7534	55	81	32	-23
12	7558	55	81	32	-23
13	7609	55	81	32	-23
14	7697	55	81	31	-24