



BALFOUR BEATTY

PROPOSED CAMBUSHINNIE 400Kv SUBSTATION
HAUL ROAD, CAMBUSHINNIE
PERTH AND KINROSS

REPORT ON GROUND INVESTIGATION

Client:

Balfour Beatty

Maxim 7

Maxim Office Park

Parklands Avenue

Eurocentral

ML1 4WQ

Contract Number: 26786

Date of Issue: 13 December 2024

Report Issue: Draft

Report Type: Factual



Raeburn Drilling & Geotechnical Limited trading as Igne.
Whistleberry Road, Hamilton ML3 0HP
Registered in Scotland No. 00094320

PROPOSED CAMBUSHINNIE 400Kv SUBSTATION
HAUL ROAD, CAMBUSHINNIE
PERTH AND KINROSS

Report Type :	Factual
Report Issue :	Draft
File Number :	Z:\26762\Report\26762 Report.docx
Contract Number :	26762
Issuing Office :	Hamilton

Originator:	
	
C J Husbands	Principal Geochemist	13 December 2024
Checked & Approved:	
	
FM Raeburn	Chief Engineer	13 December 2024

For and on Behalf of Raeburn Drilling and Geotechnical Limited Trading as Igne

This Report and its appendices has been prepared by Raeburn Drilling & Geotechnical Limited (Igne) with all reasonable skill and care, within the terms and conditions of the contract between Igne and the Client ("Contract") and within the limitations of the scope agreed with the Client. Any reliance upon the Report and its appendices is subject to the Contract terms and conditions.

This Report, its appendices and its intellectual property is confidential between the Client and Igne. Igne accepts no responsibility whatsoever to third parties to whom this document, or any part thereof is made known. Any such party relies upon the Report and its appendices at their own risk. The Contracts (Rights of Third Parties) Act 1999 does not apply to this Report and its appendices, nor the Contract and the provisions of the said Act are hereby excluded.

This report and its appendices must be read in its entirety and its intellectual property shall not be used for engineering or contractual purposes unless signed above by the author, checker and the approver for and on behalf of Igne and unless the Report status is 'Final'.

Unless specifically assigned or transferred within the terms and conditions of the Contract, Igne asserts and retains all Copyright and other Intellectual Property Rights in and over the Report contents and its appendices. The Report and its appendices may not be copied or reproduced, in whole or in part, without the written authorisation from Igne. Igne shall not be liable for any use of the Report and its appendices for any purpose other than that for which it was originally prepared.



TABLE OF CONTENTS

1. INTRODUCTION	1
2. LOCATION OF SITE	2
3. GROUND INVESTIGATION	2
3.1 SITE WORK	2
3.2 LABORATORY TESTING	4

References

Total No of Text Pages: 4

Figure

APPENDIX A: PLANS

Location Plan	A1
Site Plan	A2

APPENDIX B: SITE WORK

Notes on Field Procedures	
Key to Borehole and Trial Pit Records	
Borehole Records	B1 to B9
Trial Pit Records	B10 to B31
Photographs of Rock Core	B32 and B33
Photographs of Pavement Core	B34 to B37
Photographs of Trial Pits	B38 to B81
SPT Hammer Energy Test Report – RD53 and TERR22	B82 and B83
Dynamic Cone Penetration Records	B84 to B102
Results of Gas and Water Level Measurements	B103

APPENDIX C: GEOTECHNICAL LABORATORY TESTING

Notes on Laboratory Procedures	
Laboratory Test Results	C1 to C70
BRE Test Results – Socotec Test Report - 24112491	

APPENDIX D: GEOCHEMICAL LABORATORY TESTING

Socotec Test Report - 24111509
Socotec Test Report - 24112027

APPENDIX E: ARCHAEOLOGICAL CLERK OF WORKS REPORT

Guard Archaeology Report Ref. 6660

BALFOUR BEATTY

PROPOSED CAMBUSHINNIE 400KV SUBSTATION HAUL ROAD, CAMBUSHINNIE PERTH AND KINROSS

REPORT ON GROUND INVESTIGATION

Contract No. 26762

13 December 2024

1. INTRODUCTION

It is proposed to construct a new 400kV substation at Cambushinnie, immediately west of the existing Braco 275kV substation. Associated with the development is a haul road between Easter Feddal and the A822, via the B8033. On the instructions of Balfour Beatty and to the specification of the Designer WSP, an investigation was carried out to provide information on the ground conditions for design and construction of the proposed works and in relation to any geochemical contamination of the site. A factual report only was requested.

The comments given in this report and any opinions expressed therein are based on the ground conditions encountered during the site work, on the results of any in-situ or laboratory testing and any professional third party input. Whilst every effort has been made to ensure the accuracy of the data supplied and any analysis or interpretation derived from it, the possibility exists of variations in the ground, ground-water and ground gas conditions around, below and between the extent of the exploratory positions. No liability can be accepted for any such variations in these conditions. Furthermore, any recommendations are specific to the development as detailed in this Report and no liability will be accepted should they be used for the design of alternative schemes, by third parties, without prior consultation with Raeburn Drilling & Geotechnical Limited trading as Igne.



2. LOCATION OF SITE

The site comprises a liner route between the A822 at approximate national grid reference NN836090 and Gamekeeper's Cottage at Easter Feddal (approximate National Grid reference NN824092).

A plan showing the approximate location of the site is given in Figure A1 in Appendix A.

3. GROUND INVESTIGATION

3.1 Site Work

The site work was carried out during the period 15 to 25 October 2024, in accordance with the guidelines laid down in EN1997-2:2007 (Ref. 1), BS5930 (Ref. 2), BS10175 (Ref. 3) and in-house procedures. The results of the site work are given in Appendix B.

Two boreholes (Nos. BH01 and BH02) were sunk by rota-sonic and core drilling methods and a further seven (Nos. WS01 to WS07) were undertaken using continuous percussion boring. In addition, twenty-two trial pits (Nos. TP01 to TP22) were excavated by machine. Lastly, four pavement cores were undertaken where the route crossed tarmacked roads. All of the positions are shown on the site plan (Fig. A2 in Appendix A). The depths of the boreholes and trial pits, the descriptions of the strata encountered and comments on the ground-water conditions are given in the borehole and trial pit records (Figs. B1 to B31). The positions and depths of the boreholes, trial pits and pavement cores were determined by the Designer and were set out on site by Raeburn Drilling & Geotechnical Limited trading as Igne, in conjunction with the Designer.

Disturbed and 100mm diameter tube samples were taken at the depths shown on the borehole and trial pit records and were despatched, together with the rock cores, to the depot at Hamilton for examination and storage. Geochemical soil samples were taken directly into tubs. Samples for volatiles analysis were taken into vials, filling the container completely such that no voids were present. Geochemical samples were stored on site and transported to the laboratory in coolboxes. Each sample was uniquely identified and a transmittal note system used throughout sample transfer.



Photographs were taken of the rock core, pavement cores and the trial pits, together with the associated spoil heaps. A copy is presented as Figures B32 to B81.

Standard (split-barrel sampler) penetration tests (Ref. 4) were made to assess the relative density of the materials encountered. The values of penetration resistance, given in the borehole records, are not corrected for energy ratio, or in any other way. The references to relative density under the heading "Description of Strata" in the borehole records are based on the field values of penetration resistance uncorrected for the effects of overburden pressure. Two sets of equipment were used for the tests and the Hammer Energy Test Reports are presented as Figures B82 and B83. The set that was used in each borehole is noted in the "Remarks" section of the borehole record.

Soakaway tests (Ref. 5) were undertaken in trial pits TP03, TP09, TP10, TP11, TP12 and TP15. The results will follow publication of this report.

Dynamic Cone Penetrometer (DCP) tests (Ref. ??) were undertaken adjacent to trial pits TP01 to TP12, TP16 to TP18 and TP20 to TP22. The results are given as Figures B84 to B102, in Appendix B, which include plots of cumulative blow count against depth and California bearing ratio (CBR) against depth.

To assess the shear strength of the soils, hand vane tests (Ref. 7) were carried out within the trial pits. The depth of the tests and the results are given on the trial pit records. However, it should be recognised that the theory behind the evaluation of vane test results assumes a smooth cylindrical failure surface. Due to the presence of gravel and indeed sand, this was not the case with most of these tests. As such, many of the results are likely to be erroneously high.

A nominal 50mm diameter perforated standpipe was installed in each of boreholes BH01, BH02 and WS01 to WS04, WS06 and WS07, details of which are given on the relevant records. Tests were subsequently carried out to determine the methane, carbon dioxide, carbon monoxide, hydrogen sulphide and oxygen contents of the gas in the standpipes. In addition, water level readings were taken in the instruments. The results of the monitoring are given in Figure B_.



During the monitoring visit on 10 December 2024, the standpipes in boreholes BH01, WS01, WS02, WS03, WS04 and WS06 were purged of three well volumes. Thereafter, water samples were taken by bailer, before being transferred to one litre glass and plastic bottles. The water samples were delivered to the laboratory in coolboxes.

The ground levels and co-ordinates at the borehole and trial pit positions, given on the records, were determined using a Global Positioning System and are related to Ordnance Datum and the National Grid, respectively.

3.2 Laboratory Testing

A test schedule was forwarded by the Designer. The laboratory testing was carried out by Terra Tek Limited (trading as Igne) and Socotec Limited. Both hold UKAS Accreditation for the scheduled tests.

The geotechnical laboratory testing was carried out in accordance with the referenced testing procedures given below. The results are given in Appendix C and comprised the following:

Description of Test	Figures	Ref
Moisture Content Tests	C1 to C4	8
Liquid and Plastic Limit Tests	C5 to C15	8
Particle Size Distribution Tests	C16 to C52	8
Determination of Dry Density/Water Content Relationship	C53 to C56	9
California Bearing Ratio Tests	C57 to C61	9
Unconsolidated Undrained Single Stage Triaxial Compression Tests	C62 to C69	9
Point Load tests	C70	10
BRE Tests – Socotec Test Report – 24112491		11

In addition, chemical contamination testing was carried out on thirty-six samples of made ground/soil. As noted earlier, the analyses were undertaken by Socotec Limited and test reports 24111509 and 241122027 are presented in Appendix D.

The results of the groundwater sampling described above will follow publication of the draft report.

Finally, the works involving excavations were observed by an Archaeological Clerk of Works (ACoW) and the report from the ACoW is given in Appendix E.

Principal Geochemist

Chief Engineer

For and on Behalf of Raeburn Drilling and Geotechnical Limited Trading as Igne

Ground Investigation Department

Hamilton

This Report and its appendices has been prepared by Raeburn Drilling & Geotechnical Limited ("Igne") with all reasonable skill and care, within the terms and conditions of the contract between Igne and the Client ("Contract") and within the limitations of the scope agreed with the Client. Any reliance upon the Report and its appendices is subject to the Contract terms and conditions.

This Report, its appendices and its intellectual property is confidential between the Client and Igne. Igne accepts no responsibility whatsoever to third parties to whom this document, or any part thereof is made known. Any such party relies upon the Report and its appendices at their own risk. The Contracts (Rights of Third Parties) Act 1999 does not apply to this Report and its appendices, nor the Contract and the provisions of the said Act are hereby excluded.

This report and its appendices must be read in its entirety and its intellectual property shall not be used for engineering or contractual purposes unless signed above by the author, checker and the approver for and on behalf of Igne and unless the Report status is 'Final'.

Unless specifically assigned or transferred within the terms and conditions of the Contract, Igne asserts and retains all Copyright and other Intellectual Property Rights in and over the Report contents and its appendices. The Report and its appendices may not be copied or reproduced, in whole or in part, without the written authorisation from Igne. Igne shall not be liable for any use of the Report for any purpose other than that for which it was originally prepared.

REFERENCES

- (1) BS EN 1997-2. Eurocode 7 : Geotechnical design – Part 2 : Design assisted by laboratory testing. 2007.
- (2) BS5930:2015+A1:2020: Code of Practice for Ground Investigations, British Standards Institution, 2020.
- (3) BS10175: Code of Practice for the Investigation of Potentially Contaminated Sites, British Standards Institution, 2011 + A1:2013.
- (4) BS EN ISO 22476-3: Geotechnical investigation and testing. Field testing. Standard penetration test, 2005.
- (5) BRE Digest 365. Soakaway Design. Building Research Establishment. Sept., 1991.
- (6) <https://www.standardsforhighways.co.uk/dmrh>
- (7) BS1377-7:1990 Methods of test for soils for civil engineering purposes – shear strength tests (total stress)
- (8) BS EN ISO 17892: Geotechnical investigation and testing. Laboratory testing of soil. Parts 1 to 12. 2014 - 2018.
- (9) BS1377: Methods of Test for Soils for Civil Engineering Purposes, British Standards Institution, 1990.
- (10) Suggested Method for Determining Point Load Strength, International Society for Rock Mechanics, Commission on Testing Methods, Int. J Rock Mech. Min. Sci. and Geomech. Abstr., Vol. 22, 1985.
- (11) BRE Special Digest 1. Concrete in Aggressive Ground. Building Research Establishment. 2005.



Site: CAMBUSHINNIE 400KV SUBSTATION

Contract No: 26762

Client: Balfour Beatty

Engineer: Balfour Beatty

APPENDIX A
PLANS





Site: CAMBUSHINNIE 400KV SUBSTATION



Contract No: 26762

Client: Balfour Beatty

Crown Copyright
Licence No.

Engineer: Balfour Beatty

1000005786



LOCATION PLAN

Originator

CB

Title:

Fig No:

Chk & App

Status

CJH

Final

A1

Style: A3 SITEPLAN File: P:\GINTWP\PROJECTS\26762.GPJ Printed: 12/12/2024 16:54:46 Raaburn Drilling and Geotechnical Whisteherry Rd. Hamilton, M.S. OHP Tel: 01609 711177 Email: enquiries@raaburndrilling.com




Site: CAMBUSHINNIE 400KV SUBSTATION

Contract No: 26762

Client: Balfour Beatty

Engineer: Balfour Beatty



Exploratory Hole No.	Easting	Northing
BH01	283424.702	709082.678
BH02	283380.490	709089.882
DCP01	283627.189	709056.701
DCP02	283590.599	709061.311
DCP03	283542.695	709067.803
DCP04	283493.502	709073.450
DCP05	283444.646	709080.235
DCP06	283368.497	709093.275
DCP07	283321.139	709105.395
DCP08	283276.996	709118.940
DCP09	283212.984	709137.925
DCP10	283162.503	709150.519
DCP11	283098.064	709166.132
DCP12	283046.689	709178.727
DCP13	283007.367	709188.238
DCP14	282919.677	709191.759
DCP15	282848.944	709190.432
DCP16	282690.543	709206.230
DCP17	282645.276	709211.834
DCP18	282578.739	709203.897
DCP19	283059.065	709125.951
DCP20	283154.860	709112.387
DCP21	283005.279	709237.836
DCP22	283094.510	709224.746
PC01	283651.821	709029.368
PC02	283656.251	709061.573
PC03	283259.902	709116.462
PC04	283255.973	709132.174
PC05	282486.962	709223.119
PC06	282470.934	709236.050
TP01	283622.99	709044.647
TP02	283587.788	709074.631
TP03	283542.523	709056.241
TP04	283491.422	709086.121
TP05	283440.737	709092.358
TP06	283376.425	709072.955
TP07	283322.054	709117.453
TP08	283210.351	709125.759
TP09	283163.208	709163.293
TP10	283096.042	709154.295
TP11	283051.524	709190.439
TP12	283002.356	709177.247
TP13	282899.911	709204.305
TP14	282835.150	709185.961
TP15	282700.710	709216.435
TP16	282636.727	709203.032
TP17	282587.597	709212.792
TP18	283041.516	709126.498
TP19	283137.311	709112.935
TP20	282987.730	709238.384
TP21	283076.961	709225.294
TP22	283443.763	709060.58
WS01	283244.938	709125.423
WS02	283136.573	709152.039
WS03	282975.089	709193.034
WS04	282954.729	709192.390
WS05	282770.707	709178.392
WS06	282746.926	709185.161
WS07	282563.159	709207.205

	Originator	Title: SITE PLAN		Fig No: A2
	CB			
Chk & App	Status			
CJH	Final			



Site: CAMBUSHINNIE 400KV SUBSTATION

Contract No: 26762

Client: Balfour Beatty

Engineer: Balfour Beatty

APPENDIX B
SITE WORKS





Site: CAMBUSHINNIE 400KV SUBSTATION

Contract No: 26762

Client: Balfour Beatty

Engineer: Balfour Beatty

Boring

The standard method of boring in soil for ground investigation is known as the cable tool method. It uses various tools worked on a wire cable, typically a shell in non-cohesive soils such as sand and gravel, and a clay cutter in cohesive soils such as clay. Very dense soils, boulders or other hard obstructions are disturbed or broken up by chiselling and the fragments removed with the shell. Where the ground conditions require, the borehole is lined with driven steel casings of such sizes that the bottom of the borehole is not less than 125mm diameter.

Where there are constraints upon access, alternative methods of soft ground boring are available. However, each has limitations that need to be taken into account when assessing their suitability and the ground conditions inferred from their results.

Rotary Drilling

Rotary drilling is employed to extend ground investigation beyond the practical limit of cable tool boring in hard formations, commonly rock. Core drilling is used to obtain continuous intact samples of the formation and is generally undertaken with double tube swivel type core barrels fitted with tungsten or diamond bits as appropriate to formation type and hardness. Open-hole rotary drilling using tricone rock roller bits or tungsten insert drag bits, or down-the-hole hammers, is carried out where more limited information is sufficient, strata identification being made from cuttings only. Open-hole rotary drilling methods may also be employed for fast penetration of soils where detailed sampling is not required, prior to coring at depth. Air or water is the flushing medium normally used with rotary drilling methods. Where the ground conditions require, the borehole is lined with inserted or drilled-in casing. Rotary percussion allows dynamic sampling within soils.

Sonic Drilling

Sonic drilling is employed as an alternative boring method for soft ground and rock. The sonic rig operates much like any conventional top-drive rotary rig. The main difference is that a sonic drill rig has a specially designed hydraulically powered drill head or oscillator which produces adjustable high frequency vibratory forces. Sonic samples are extruded direct to plastic liner bags or semi-rigid plastic liners for rapid inspection. Bulk and small disturbed samples are then taken from the plastic liner bags.

Trial Pits

Trial pits are excavated by hand or machine for a number of purposes such as avoiding services, exposing foundations or obtaining a better view of shallow ground conditions.

Samples and In-situ Tests

Tube samples of cohesive soils are generally taken with a 100mm internal diameter open drive sampler known as a U100, with an area ratio of 30%. The sampler is driven into the soil at the bottom of the borehole by a sliding hammer. After a sample is taken, the drive head and cutting shoe are unscrewed from the sample tube and any wet or disturbed soil removed from either end. The sample tube is then sealed with wax and fitted with plastic end caps.

A range of more specialised equipment, e.g. thin walled open drive sampler (UT100), piston or foil samplers, may be used to obtain higher quality samples in conditions where conventional open drive sampling is impracticable or unsatisfactory. The UT100 sampler is specifically utilised to obtain class 1 samples of cohesive soils as required under BS EN1997-2.

Disturbed samples are taken from the boring tools or trial pits at regular intervals. The samples are sealed in airtight containers. Bulk samples are large disturbed samples from the boring tools, or from trial pits, generally where tube samples are unavailable.

The Standard Penetration Test, SPT, in accordance with BS EN ISO 22476-3, determines the resistance of soil to the penetration of a split barrel sampler. A 50mm diameter split barrel sampler is driven 450mm into the soil using a 63.5kg hammer with a 760mm drop, and the penetration resistance, the "N" value, is expressed as the number of blows required to achieve 300mm penetration below an initial penetration of 150mm, the seating drive, through any disturbed soil at the bottom of the borehole.

In coarse soils, the Cone Penetration Test (CPT) is conducted in the same manner as the SPT but using a 50mm diameter 60 degree apex solid cone point to replace the split barrel sampler.

Peat Probing

Generally, peat probing is carried out using a Mackintosh Probe. The probe is pushed through the peat until resistance is met then the depth at which this occurred is recorded.

Groundwater

Borehole water levels are recorded, together with the depths at which seepages or inflows of groundwater are detected and the observations noted on the borehole or trial pit records. These observations may not give an accurate indication of groundwater conditions, for the following reasons:

- The trial pit or borehole is rarely left standing at the relevant depth for sufficient time for the water level to reach equilibrium.
- A permeable stratum may have been sealed off by the borehole casing.
- It may have been necessary to add water to the borehole to facilitate progress.
- There may be seasonal, tidal or other effects at the site.

A more accurate record of groundwater behaviour may be obtained from standpipes or standpipe piezometers.

Gases

Determination and measurement of gases in the ground, commonly in relation to landfills, may be made directly from the ground surface, where a hole is formed by driving a solid and rigid steel spike to depths normally in the range 1.0 to 1.5m. Gas emissions are analysed using an appropriate portable analyser. However, research has shown that the small sample hole size and smearing effects can give a false negative result.

Where more accurate or longer term measurement of emissions is required, gas monitoring standpipes are installed in boreholes.





Site: CAMBUSHINNIE 400KV SUBSTATION

Contract No: 26762

Client: Balfour Beatty

Engineer: Balfour Beatty

SOIL SAMPLES

U (X) General purpose tube sample; X No of blows to drive sampler

Piston Piston sample

NOTE: Tube samples are 100mm diameter unless otherwise specified in the remarks. Suffix 'a' indicates sample not recovered; suffix 'b' indicates full penetration of sampler not obtained;
suffix 'c' indicates full penetration of sampler but limited recovery

D/J/T/V Small Disturbed/Jar/Tub/Vial sample

B/LB Bag/Large Bag sample

UT (X) Thin walled push in sampler (type OS-T/W); X No of blows to drive sampler

ET Sample appropriate for geochemical analyses (tub)

CORE RECOVERY AND ROCK QUALITY

C Core Sample

TCR Total Core Recovery: The total core recovered expressed as a percentage of the core run length

SCR Solid Core Recovery: The core recovered as solid cylinders expressed as a percentage of the core run length

RQD Rock Quality Designation: The core recovered as solid cylinders of length 100mm or more expressed as a percentage of core run length.

RO-S/RO-R Rotary Open Hole Drilling through Soil / Rotary Open Hole Drilling through Rock

FI Fracture Index: The number of discontinuities expressed as fractures per metre

Flush "Depth" indicates depth down to which recorded "Returns" relate

NI Non Intact

NR No Recovery (assumed)

GROUND-WATER

W Water Sample



Ground-water encountered



Depth to which ground-water rose



Ground-water cut off by the casing

WS Water Sample from Standpipe

IN SITU AND FIELD TESTS

SPT=X a/b (pen) Standard penetration test (split barrel sampler(SPT)or cone (CPT)); X is the penetration (N) value;

or

CPT=X a/b (pen) 'a' is blow/75mm for seating drive; 'b' is blows/75mm for test drive; (pen) is test drive penetration if less than 300mm.

CBR California bearing ratio test

MCV Moisture condition value test

K Permeability test

HP Hand penetrometer test

FV Field vane test

HV Hand vane test (I = Initial, R = Residual)

ID Density test

PID Photo Ionisation Detector (ppm)

LEGENDS

Material legends are in accordance with ISO 710-1 and 710-2

before a description indicates that it is based on the Driller's record.

INSTALLATIONS (BACKFILL)



Concrete



Bentonite



Spoil



Bentonite/cement grout



Sand



Solid pipe



Gravel



Slotted pipe



Porous element



Wooden plug



Asphalt

DIMENSIONS

All dimensions in metres unless otherwise stated.

ROTARY DRILLING SIZES


Letter	Nominal Diameter (mm)	
	Borehole	Core
Standard		
N	76	54
H	100	76
P	121	92
S	146	113
Non-standard		
412	108	75


Other casing and borehole diameter sizes are available and may be used where required. Details will be on the individual BH logs.

KEY TO BOREHOLE AND TRIAL PIT RECORDS




Style: BOREHOLE NEW File: P:\GINTWP\PROJECTS\26762.GPJ-44 (0)1698 710999 Printed: 13/12/2024 10:00:33 Raeburn Drilling and Geotechnical trading as IGNE, Whistleberry Rd, Hamilton ML3 0HP Tel: 01698-711177 E-mail: enquiries.raeburndrilling@igne.com


				Site: CAMBUSHINNIE 400KV SUBSTATION										Contract No: 26762			
				Client: Balfour Beatty Engineer: Balfour Beatty										BH01 <div>Inspection Pit to 1.20m Sonic Boring to 17.70m Sonic Coring to 20.70m</div>			
Location:				Orientation: Vertical				Equipment: Hand Tools, Track Mounted Boart Longyear LS250 Mini Sonic; T2-101 Core Barrel; Water Flush									
Progress	Samples		Tests				Casing Depth	Level (mAOD)	Depth	Description of Strata				Legend	Water Depth	Backfill	
	Depth	Type	Depth	Result												Symbol	Depth
			10.20	SPT=19 2.2 /4.4.5.6			10.20										
	11.70-11.70	UT(16)								12.20							
			13.20	SPT=17 2.1 /3.4.5.5			13.20										
	14.70-14.70	UT(27)															
			16.20	SPT>50 2.2 /6.10.20.14 (240)			16.20			16.50							
				TCR	SCR	RQD	FI			17.70							
			17.70	150	150	65	>20										
							10										
							20										
							7										
			19.20	150	150	64	10										
Remarks: # Description based on Driller's log. An inspection pit was excavated by hand to a depth of 1.20m to clear services. No ground-water observations are recorded due to the use of water flush. The Penetration Tests were carried out using Trip Hammer RD53.															Hole Diam.	To Depth	Casing
															150	17.70	17.70
															101	20.70	
Driller CT	Originator JDUD	Ground-water				Water Added		Chiselling			Flush				Fig No: B1 Sheet 2 of 3 Scale 1:50		
		Struck	Rose To	Time(min)	Cut Off	From	To	From	To	hh:mm	Returns	Type	From (m)	To (m)			
Chk & App FMR	Status Final										100	Water	1.20	20.70			

				Site: CAMBUSHINNIE 400KV SUBSTATION										Contract No: 26762						
				Client: Balfour Beatty										BH01						
				Engineer: Balfour Beatty										Inspection Pit to 1.20m Sonic Boring to 17.70m Sonic Coring to 20.70m						
Location:				Orientation: Vertical				Equipment: Hand Tools, Track Mounted Boart Longyear LS250 Mini Sonic; T2-101 Core Barrel; Water Flush												
Progress	Samples		Tests				Level	Depth	Description of Strata						Legend	Water Depth	Backfill			
	Depth	Type	Depth	Result			Casing Depth										(mAOD)	Symbol	Depth	
23/10			19.20				7		17.70	20.70	END OF BOREHOLE							3.10m		20.70
Remarks:																	Hole Diam.	To Depth		
# Description based on Driller's log.																	150	Boring	Casing	
An inspection pit was excavated by hand to a depth of 1.20m to clear services.																	101	17.70	17.70	
No ground-water observations are recorded due to the use of water flush.																		20.70		
The Penetration Tests were carried out using Trip Hammer RD53.																				
Driller CT	Originator JDUD	Ground-water				Water Added		Chiselling			Flush				Fig No: B1 Sheet 3 of 3 Scale 1:50					
		Struck	Rose To	Time(min)	Cut Off	From	To	From	To	hh:mm	Returns	Type	From (m)	To (m)						
Chk & App FMR	Status Final										100	Water	1.20	20.70						


Style: BOREHOLE NEW File: P:\GINTWP\PROJECTS\26762.GPJ-44 (0)1698 710999 Printed: 13/12/2024 10:00:34 Raeburn Drilling and Geotechnical trading as IGNE, Whistleberry Rd, Hamilton ML3 0HP Tel: 01698-711177 E-mail: enquiries.raeburndrilling@igne.com




Remarks: # Description based on Driller's log. An inspection pit was excavated by hand to a depth of 1.20m to clear services. No ground-water observations are recorded due to the use of water flush. The Penetration Tests were carried out using Trip Hammer RD53. A 50mm diameter perforated standpipe was installed to a depth of 10.00m.	Hole Diam.	To Depth	
		Boring	Casing
	150 101	14.70 17.70	14.70

Driller	Originator	Ground-water				Water Added		Chiselling		Flush					Fig No:	
CT	JDUD	Struck	Rose To	Time(min)	Cut Off	From	To	From	To	hh:mm	Returns	Type	From (m)			To (m)
Chk & App FMR	Status Final										100	Water	1.20			17.70

B2
Sheet 1 of 2
Scale 1:50




Remarks: # Description based on Driller's log. An inspection pit was excavated by hand to a depth of 1.20m to clear services. No ground-water observations are recorded due to the use of water flush. The Penetration Tests were carried out using Trip Hammer RD53. A 50mm diameter perforated standpipe was installed to a depth of 10.00m.	Hole Diam.	To Depth	
		Boring	Casing
	150 101	14.70 17.70	14.70


Driller	Originator	Ground-water				Water Added		Chiselling		Flush					Fig No:	
CT	JDUD	Struck	Rose To	Time(min)	Cut Off	From	To	From	To	hh:mm	Returns	Type	From (m)			To (m)
Chk & App FMR	Status Final										100	Water	1.20			17.70


B2
Sheet 2 of 2
Scale 1:50

Printed: 13/12/2024 10:00:43
 File: P:\GINTWP\PROJECTS\26762.GPJ+44 (0)1698 711999
 Style: BOREHOLE NEW
 Raeburn Drilling and Geotechnical trading as GNE, Whistleberry Rd, Hamilton ML3 0HP Tel: 01698-711177 E-mail: enquiries.raeburndrilling@igne.com




Remarks: # Description based on Driller's log. An inspection pit was excavated by hand to a depth of 1.20m to clear services. Ground-water was encountered at a depth of 2.50m. The Penetration Tests were carried out using Trip Hammer TERR22. The borehole was terminated at 4.65m on an obstruction. A 50mm diameter perforated standpipe was installed to a depth of 3.00m.	To Depth	
	Boring	Casing
	110	4.65

Driller JW	Originator JDUD	Ground-water			Cut Off	Water Added		Chiselling		hh:mm	Returns	Flush			Fig No:
		Struck	Rose To	Time(min)		From	To	From	To			Type	From (m)		
Chk & App FMR	Status Final	2.50	2.05	5.00											B3 Sheet 1 of 1 Scale 1:50
		2.50	2.05	10.00											
		2.50	2.05	15.00											
		2.50	2.05	20.00											





Remarks: # Description based on Driller's log. An inspection pit was excavated by hand to a depth of 1.20m to clear services. Ground-water was encountered at a depth of 1.20m. The Penetration Tests were carried out using Trip Hammer TERR22. A 50mm diameter perforated standpipe was installed to a depth of 4.65m.	To Depth	
	Boring	Casing
	110	5.00

Style: BOREHOLE NEW File: P:\GINTWP\PROJECTS\26762.GPJ+44 (0)1698 719999 Printed: 13/12/2024 10:00:51
Raeburn Drilling and Geotechnical trading as GNE, Whistleberry Rd, Hamilton ML3 0HP Tel: 01698-711177 E-mail: enquiries.raeburndrilling@igne.com





Remarks: # Description based on Driller's log. An inspection pit was excavated by hand to a depth of 1.20m to clear services. Ground-water was encountered at a depth of 1.20m. The Penetration Tests were carried out using Trip Hammer TERR22. The borehole was terminated 3.50m on an obstruction. A 50mm diameter perforated standpipe was installed to a depth of 3.50m.	To Depth	
	Boring	Casing
	110	3.50

Driller JW	Originator JDUD	Ground-water			Cut Off	Water Added		Chiselling		Flush					Fig No:	
		Struck	Rose To	Time(min)		From	To	From	To	hh:mm	Returns	Type	From (m)			To (m)
Chk & App FMR	Status Final	1.20	1.00	5.00												B5 Sheet 1 of 1 Scale 1:50
		1.20	1.00	10.00												
		1.20	0.80	15.00												
		1.20	0.75	20.00												





Remarks:	To Depth	
	Boring	Casing
	110	2.20

Driller JW	Originator JDUD	Ground-water			Cut Off	Water Added		Chiselling		hh:mm	Returns	Flush			Fig No:
		Struck	Rose To	Time(min)		From	To	From	To			Type	From (m)		
Chk & App FMR	Status Final	1.10	0.90	5.00											B6 Sheet 1 of 1 Scale 1:50
		1.10	0.90	10.00											
		1.10	0.90	15.00											
		1.10	0.90	20.00											





Remarks: # Description based on Driller's log. An inspection pit was excavated by hand to a depth of 1.20m to clear services. Ground-water was encountered at a depth of 1.10m. The borehole was terminated at 2.80m on an obstruction. The Penetration Tests were carried out using Trip Hammer TERR22.	To Depth	
	Boring	Casing
	110	2.80

Driller JW	Originator JDUD	Ground-water				Water Added		Chiselling		Flush					Fig No:	
		Struck	Rose To	Time(min)	Cut Off	From	To	From	To	hh:mm	Returns	Type	From (m)			To (m)
Chk & App FMR	Status Final	1.00	0.80	5.00	2.20											B7 Sheet 1 of 1 Scale 1:50
		1.00	0.70	10.00												
		1.00	0.70	15.00												
		1.00	0.60	20.00												





Remarks:	To Depth	
	Boring	Casing
	110	3.55 3.20

Driller JW	Originator JDUD	Ground-water			Cut Off	Water Added		Chiselling		hh:mm	Returns	Flush			Fig No:
		Struck	Rose To	Time(min)		From	To	From	To			Type	From (m)		
Chk & App FMR	Status Final	1.00	0.80	5.00											B8 Sheet 1 of 1 Scale 1:50
		1.00	0.75	10.00											
		1.00	0.70	15.00											
		1.00	0.65	20.00											




Remarks:	To Depth	
	Boring	Casing
	110	3.40


Driller JW	Originator JDUD	Ground-water				Water Added		Chiselling		Flush					Fig No:	
		Struck	Rose To	Time(min)	Cut Off	From	To	From	To	hh:mm	Returns	Type	From (m)			To (m)
Chk & App FMR	Status Final	1.00	0.90	5.00	0.90											B9 Sheet 1 of 1 Scale 1:50
		1.00	0.90	10.00												
		1.00	0.90	15.00												
		1.00	0.90	20.00												




Remarks:	Hole	To Depth	
	Diam.	Boring	Casing
Trial pit CAT scanned prior to excavation to check for services. Ground-water was encountered at a depth of 2.20m as rapid ingress. The walls of the pit stood vertical throughout excavation. Trial pit terminated at a depth of 2.40m due to ground-water ingress.			

Driller	Originator RJB	Ground-water				Water Added		Chiselling			Flush					Fig No:
		Struck 2.20	Rose To	Time(min)	Cut Off	From	To	From	To	hh:mm	Returns	Type	From (m)	To (m)		
Chk & App FMR	Status Final															B10 Sheet 1 of 1 Scale 1:50

Site: CAMBUSHINNIE 400KV SUBSTATION		Contract No: 26762
Client: Balfour Beatty		Trial Pit No. TP02
Engineer: Balfour Beatty		Trial Pit to 1.90m
Vertical	Equipment: 8T Tracked Excavator	Width - 1.80m Length - 2.50m







Remarks: Trial pit CAT scanned prior to excavation to check for services. Ground-water was not encountered. The walls of the pit collapsed throughout excavation - sidewalls collapsed. Trial pit terminated at a depth of 3.00m due to sidewall collapse.	To Depth	
	Hole Diam.	
	Boring	Casing

Driller	Originator RJB	Ground-water				Water Added		Chiselling			Flush					Fig No:
		Struck	Rose To	Time(min)	Cut Off	From	To	From	To	hh:mm	Returns	Type	From (m)	To (m)		
Chk & App FMR	Status Final															B13 Sheet 1 of 1 Scale 1:50

Printed: 13/12/2024 10:02:21
 File: P:\GINTWP\PROJECTS\26762.GPJ+44 (0)1698 710999
 Style: BOREHOLE NEW
 Raeburn Drilling and Geotechnical trading as IGNE, Whistleberry Rd, Hamilton ML3 0HP Tel: 01698-711177 E-mail: enquiries.raeburndrilling@igne.com






Remarks: Trial pit CAT scanned prior to excavation to check for services. Ground-water was not encountered. The walls of the pit collapsed throughout excavation - sidewalls collapsed. Trial pit terminated at a depth of 3.10m due to sidewall collapse.	To Depth	
	Hole Diam.	
	Boring	Casing





Driller	Originator RJB	Ground-water				Water Added		Chiselling		hh:mm	Flush					Fig No:
		Struck	Rose To	Time(min)	Cut Off	From	To	From	To	Returns	Type	From (m)	To (m)			
Chk & App FMR	Status Final														B14 Sheet 1 of 1 Scale 1:50	

Printed: 13/12/2024 10:02:23
 File: P:\GINTWP\PROJECTS\26762.GPJ+44 (0)1698 710999
 Style: BOREHOLE NEW
 Raeburn Drilling and Geotechnical trading as IGNE, Whistleberry Rd, Hamilton ML3 0HP Tel: 01698-711177 E-mail: enquiries.raeburndrilling@igne.com


Site: CAMBUSHINNIE 400KV SUBSTATION		Contract No: 26762
Client: Balfour Beatty		Trial Pit No. TP06
Engineer: Balfour Beatty		Trial Pit to 2.90m
Vertical	Equipment: 8T Tracked Excavator	Width - 1.70m Length - 2.80m


Style: BOREHOLE NEW File: P:\GINTWP\PROJECTS\26762.GPJ-44 (0)1698 710999 Printed: 13/12/2024 10:02:28 Raeburn Drilling and Geotechnical trading as IGNE Whistleberry Rd, Hamilton ML3 0HP Tel: 01698-711177 E-mail: enquiries.raeburndrilling@igne.com

		Site: CAMBUSHINNIE 400KV SUBSTATION										Contract No: 26762		
		Client: Balfour Beatty Engineer: Balfour Beatty										Trial Pit No. TP07		
												Trial Pit to 2.50m		
Location:			Orientation: Vertical			Equipment: 8T Tracked Excavator							Width - 1.60m Length - 2.80m	
Progress 17/10/2024	Samples		Tests		Casing Depth	Level (mAOD)	Depth	Description of Strata	Legend	Water Depth	Backfill			
	Depth	Type	Depth	Result							Symbol	Depth		
	0.50	B, D, ES					0.60	Light brown gravelly slightly silty fine to coarse SAND with medium cobble content. Gravel is fine to coarse angular to subrounded of sandstone and mudstone. Cobbles are angular to subrounded of sandstone						
	1.50	D, ES						Light brown very sandy silty fine to coarse angular to subrounded GRAVEL of mudstone and sandstone with low cobble content. Sand is fine to coarse. Cobbles are angular and subangular of sandstone						
17/10	2.50	B, D, ES					2.50	END OF BOREHOLE		2.30m		2.50		
Remarks: Trial pit CAT scanned prior to excavation to check for services. Ground-water was encountered at a depth of 2.30m as rapid ingress. The walls of the pit collapsed throughout excavation - sidewalls collapsed. Trial pit terminated at a depth of 2.50m due to sidewall collapse and ground-water ingress.												Hole Diam.	To Depth Boring Casing	
Driller	Originator RB	Ground-water Struck 2.30 Rose To Time(min) Cut Off				Water Added From To		Chiselling From To hh:mm		Flush Returns Type From (m) To (m)		Fig No: B16 Sheet 1 of 1 Scale 1:50		
Chk & App FMR	Status Final													


		Site: CAMBUSHINNIE 400KV SUBSTATION										Contract No: 26762					
		Client: Balfour Beatty Engineer: Balfour Beatty										Trial Pit No. TP08					
		Location: Orientation: Vertical Equipment: 8T Tracked Excavator										Trial Pit to 2.20m					
														Width - 1.60m Length - 1.80m			
Progress 17/10/2024	Samples		Tests		Casing Depth	Level (mAOD)	Depth	Description of Strata	Legend	Water Depth	Backfill						
	Depth	Type	Depth	Result							Symbol	Depth					
	0.20	D, ES						Light brown gravelly slightly silty fine to coarse SAND with cobbles. Gravel is fine to coarse angular and subangular of sandstone and mudstone. Cobbles are angular to subrounded of sandstone		1.90m		2.20					
	0.50	LB				0.70											
	1.20	D, ES					Light brown very sandy silty fine to coarse angular to subrounded GRAVEL of mudstone and sandstone with medium cobble content. Sand is fine to coarse. Cobbles are angular and subangular of sandstone and mudstone										
17/10	2.20	B, D, ES, LB					2.20	END OF BOREHOLE									
Remarks: Trial pit CAT scanned prior to excavation to check for services. Ground-water was encountered at a depth of 1.90m as rapid ingress. The walls of the pit collapsed throughout excavation - sidewalls collapsed. Trial pit terminated at a depth of 2.20m due to sidewall collapse and ground-water ingress.										Hole Diam.	To Depth Boring Casing						
Driller	Originator RJB	Ground-water				Water Added		Chiselling		Flush			Fig No: B17 Sheet 1 of 1 Scale 1:50				
		Struck	Rose To	Time(min)	Cut Off	From	To	From	To	hh:mm	Returns			Type	From (m)	To (m)	
Chk & App FMR	Status Final	1.90															


Style: BOREHOLE NEW File: P:\GINTWP\PROJECTS\26762.GPJ-44 (0)1698 710999 Printed: 13/12/2024 10:02:31 Raeburn Drilling and Geotechnical trading as IGNE Whistleberry Rd, Hamilton ML3 0HP Tel: 01698-711177 E-mail: enquiries.raeburndrilling@igne.com









Remarks:	Hole Diam.	To Depth	
		Boring	Casing
<p>Trial pit CAT scanned prior to excavation to check for services.</p> <p>Ground-water was encountered at a depth of 1.70m as moderate inflow.</p> <p>The walls of the pit collapsed throughout excavation - sidewalls collapsed.</p> <p>Trial pit terminated at a depth of 2.00m due to sidewall collapse.</p>			

Driller	Originator RJB	Ground-water				Water Added		Chiselling			Flush					Fig No:
		Struck 1.70	Rose To	Time(min)	Cut Off	From	To	From	To	hh:mm	Returns	Type	From (m)	To (m)		
Chk & App FMR	Status Final															B19 Sheet 1 of 1 Scale 1:50




Remarks:	Hole	To Depth	
	Diam.	Boring	Casing
Trial pit CAT scanned prior to excavation to check for services. Ground-water was encountered at a depth of 1.85m as rapid ingress. The walls of the pit collapsed throughout excavation - sidewalls collapsed. Trial pit terminated at a depth of 1.90m due to sidewall collapse.			

Driller	Originator RJB	Ground-water				Water Added		Chiselling			Flush					Fig No:
		Struck 1.85	Rose To	Time(min)	Cut Off	From	To	From	To	hh:mm	Returns	Type	From (m)	To (m)		
Chk & App FMR	Status Final															B20 Sheet 1 of 1 Scale 1:50


		Site: CAMBUSHINNIE 400KV SUBSTATION										Contract No: 26762								
		Client: Balfour Beatty Engineer: Balfour Beatty										Trial Pit No. TP12								
												Trial Pit to 2.20m								
Location:				Orientation: Vertical				Equipment: 8T Tracked Excavator												
Width - 1.60m Length - 1.80m																				
Progress 17/10/2024	Samples		Tests		Casing Depth	Level (mAOD)	Depth	Description of Strata						Legend	Water Depth	Backfill				
	Depth	Type	Depth	Result												Symbol	Depth			
	0.20	D, ES, LB					0.60	Dark greyish brown slightly gravelly clayey fine to coarse SAND with low cobble content. Gravel is fine to coarse angular to subrounded of sandstone												
	1.20	D, ES						Reddish brown gravelly silty fine to coarse SAND with medium cobble content. Gravel is fine to coarse angular to subrounded of sandstone. Cobbles are angular to subrounded of sandstone												
18/10	2.20	D, ES, LB					2.20	END OF BOREHOLE											Dry	
Remarks: Trial pit CAT scanned prior to excavation to check for services. Ground-water was not encountered. The walls of the pit collapsed throughout excavation - sidewalls collapsed. Trial pit terminated at a depth of 2.20m due to sidewall collapse.																		Hole Diam.	To Depth	
																			Boring	Casing
Driller	Originator RJB	Ground-water				Water Added		Chiselling			Flush				Fig No: B21 Sheet 1 of 1 Scale 1:50					
		Struck	Rose To	Time(min)	Cut Off	From	To	From	To	hh:mm	Returns	Type	From (m)	To (m)						
Chk & App FMR	Status Final																			

Style: BOREHOLE NEW File: P:\GINTWP\PROJECTS\26762.GPJ-44 (0)1698 710999 Printed: 13/12/2024 10:02:43 Raeburn Drilling and Geotechnical trading as IGNE, Whistleberry Rd, Hamilton ML3 0HP Tel: 01698-711177 E-mail: enquiries.raeburndrilling@igne.com




Remarks: Trial pit CAT scanned prior to excavation to check for services. Ground-water was not encountered. The walls of the pit stood vertical throughout excavation. Trial pit terminated at a depth of 3.20m due to obstruction - possible bedrock.	Hole	To Depth	
	Diam.	Boring	Casing

Driller	Originator RJB	Ground-water				Water Added		Chiselling			Flush					Fig No:
		Struck	Rose To	Time(min)	Cut Off	From	To	From	To	hh:mm	Returns	Type	From (m)	To (m)		
Chk & App FMR	Status Final															B22 Sheet 1 of 1 Scale 1:50





Remarks: Trial pit CAT scanned prior to excavation to check for services. Ground-water was not encountered. The walls of the pit stood vertical throughout excavation. Trial pit terminated at a depth of 3.20m due to undermining of excavator due to restrictions on pit size due to landowner's restrictions.	Hole	To Depth	
	Diam.	Boring	Casing

Driller	Originator RJB	Ground-water				Water Added		Chiselling			Flush					Fig No:
		Struck	Rose To	Time(min)	Cut Off	From	To	From	To	hh:mm	Returns	Type	From (m)	To (m)		
Chk & App FMR	Status Final															B23 Sheet 1 of 1 Scale 1:50

		Site: CAMBUSHINNIE 400KV SUBSTATION										Contract No: 26762															
		Client: Balfour Beatty Engineer: Balfour Beatty										Trial Pit No. TP16															
												Trial Pit to 2.00m															
Location:				Orientation: Vertical				Equipment: 8T Tracked Excavator																			
Width - 1.80m Length - 2.80m																											
Progress 25/10/2024	Samples		Tests		Casing Depth	Level (mAOD)	Depth	Description of Strata						Legend	Water Depth	Backfill											
	Depth	Type	Depth	Result												Symbol	Depth										
	0.50	D, ES						Dark brown gravelly silty fine to coarse SAND with decomposed rootlets. Gravel is fine to coarse subangular to rounded of sandstone and mudstone																			
	1.00	LB																									
	1.50	D, ES					1.50	Brown slightly gravelly slightly sandy SILT. Sand is fine to coarse. Gravel is fine to coarse angular to subrounded of sandstone																			
25/10							2.00	END OF BOREHOLE							1.95m	2.00											
Remarks: Trial pit CAT scanned prior to excavation to check for services. Ground-water was encountered at a depth of 1.90m as rapid ingress. The walls of the pit collapsed throughout excavation. Trial pit terminated at a depth of 2.00m due to ground-water ingress and sidewall collapse.																		Hole Diam.	To Depth								
																			Boring	Casing							
Driller		Originator		Ground-water				Water Added		Chiselling		Flush				Fig No: B25 Sheet 1 of 1 Scale 1:50											
		RJB		Struck	Rose To	Time(min)	Cut Off	From	To	From	To	hh:mm	Returns	Type	From (m)			To (m)									
Chk & App FMR		Status Final		1.90																							

Style: BOREHOLE NEW File: P:\GINTWP\PROJECTS\26762.GPJ-44 (0)1698 710999 Printed: 13/12/2024 10:02:52 Raeburn Drilling and Geotechnical trading as IGNE, Whistleberry Rd, Hamilton ML3 0HP Tel: 01698-711177 E-mail: enquiries.raeburndrilling@igne.com











Remarks:	Hole	To Depth	
	Diam.	Boring	Casing
<p>Trial pit CAT scanned prior to excavation to check for services.</p> <p>Groundwater was encountered as seepage below 1.90m.</p> <p>The walls of the pit collapsed throughout excavation - sidewalls collapsed.</p> <p>Trial pit terminated at a depth of 2.60m due to sidewall collapse.</p>			


Driller	Originator RJB	Ground-water				Water Added		Chiselling			Flush					Fig No:
		Struck	Rose To	Time(min)	Cut Off	From	To	From	To	hh:mm	Returns	Type	From (m)	To (m)		
Chk & App FMR	Status Final															B27 Sheet 1 of 1 Scale 1:50

Style: BOREHOLE NEW File: P:\GINTWP\PROJECTS\26762.GPJ-44 (0)1698 710999 Printed: 13/12/2024 10:02:59 Raeburn Drilling and Geotechnical trading as IGNE, Whistleberry Rd, Hamilton ML3 0HP Tel: 01698-711177 E-mail: enquiries.raeburndrilling@igne.com


		Site: CAMBUSHINNIE 400KV SUBSTATION										Contract No: 26762			
		Client: Balfour Beatty Engineer: Balfour Beatty										Trial Pit No. TP19			
												Trial Pit to 1.90m			
Location:			Orientation: Vertical			Equipment: 8T Tracked Excavator							Width - 1.80m Length - 2.50m		
Progress 21/10/2024	Samples		Tests		Casing Depth	Level (mAOD)	Depth	Description of Strata	Legend	Water Depth	Backfill Symbol	Backfill Depth			
	Depth	Type	Depth	Result											
	0.30												Dark brown slightly gravelly clayey fine to coarse SAND. Gravel is fine to coarse subangular and subrounded of sandstone		
	0.50	D, ES											Light brown gravelly slightly clayey fine to coarse SAND. Gravel is fine to coarse angular to subrounded of sandstone		
	0.90												Light grey very sandy slightly silty fine to coarse angular to subrounded GRAVEL of sandstone with low cobble content. Sand is fine to coarse. Cobbles are angular and subangular of sandstone. Locally passing to silty sand and gravel		
1.00	LB														
1.50	D, ES														
21/10						1.90	END OF BOREHOLE						1.85m	1.90	
Remarks: Trial pit CAT scanned prior to excavation to check for services. Ground-water was encountered at a depth of 1.70m as rapid inflow. The walls of the pit collapsed throughout excavation - sidewalls collapsed. Trial pit terminated at a depth of 1.90m due to sidewall collapse.												Hole Diam.	To Depth Boring Casing		
Driller	Originator RJB	Ground-water Struck 1.70 Rose To Time(min) Cut Off				Water Added From To		Chiselling From To hh:mm		Flush Returns Type From (m) To (m)				 Fig No: B28 Sheet 1 of 1 Scale 1:50	
Chk & App FMR	Status Final														

Style: BOREHOLE NEW File: P:\GINTWP\PROJECTS\26762.GPJ-44 (0)1698 710999 Printed: 13/12/2024 10:03:02 Raeburn Drilling and Geotechnical trading as IGNE, Whistleberry Rd, Hamilton ML3 0HP Tel: 01698-711177 E-mail: enquiries.raeburndrilling@igne.com

			Site: CAMBUSHINNIE 400KV SUBSTATION										Contract No: 26762	
			Client: Balfour Beatty Engineer: Balfour Beatty										Trial Pit No. TP20	
													Trial Pit to 3.00m	
Location:			Orientation: Vertical				Equipment: 8T Tracked Excavator					Width - 1.60m Length - 1.80m		
Progress 17/10/2024	Samples		Tests		Casing Depth	Level (mAOD)	Depth	Description of Strata	Legend	Water Depth	Backfill			
	Depth	Type	Depth	Result							Symbol	Depth		
17/10	0.20	D, ES	0.80	HV at 0.80m I=40 R=10kPa HV at 0.80m I=28 R=10kPa HV at 0.80m I=22 R=10kPa			0.60	Light brown gravelly slightly clayey fine to coarse SAND with low cobble content. Gravel is fine to coarse angular to subrounded. Cobbles are angular to subrounded of sandstone						
	0.50	LB						Firm dark brown slightly gravelly sandy CLAY. Sand is fine to coarse. Gravel is fine to coarse subangular and subrounded of sandstone						
	1.20	D, ES						Light brown very gravelly clayey fine to coarse SAND with low cobble content. Gravel is fine to coarse angular to subrounded. Cobbles are angular to subrounded of sandstone						
	2.20	D, ES												
	2.50	LB												
	3.00													
END OF BOREHOLE									2.70m		3.00			
Remarks: Trial pit CAT scanned prior to excavation to check for services. Ground-water was encountered at a depth of 2.50m as moderate inflow. The walls of the pit collapsed throughout excavation - sidewalls collapsed. Trial pit terminated at a depth of 3.00m due to sidewall collapse.										Hole Diam.	To Depth Boring Casing			
Driller	Originator RJB	Ground-water Struck 2.50 Rose To Time(min) Cut Off				Water Added From To		Chiselling From To hh:mm		Flush Returns Type From (m) To (m)			Fig No: B29 Sheet 1 of 1 Scale 1:50	
Chk & App FMR	Status Final													

		Site: CAMBUSHINNIE 400KV SUBSTATION										Contract No: 26762															
		Client: Balfour Beatty Engineer: Balfour Beatty										Trial Pit No. TP21															
												Trial Pit to 3.10m															
Location:				Orientation: Vertical				Equipment: 8T Tracked Excavator																			
Width - 1.80m Length - 2.50m																											
Progress 21/10/2024	Samples		Tests		Casing Depth	Level (mAOD)	Depth	Description of Strata						Legend	Water Depth	Backfill											
	Depth	Type	Depth	Result												Symbol	Depth										
	1.00	D, ES, LB					0.35	Dark brown slightly gravelly clayey fine to coarse SAND. Gravel is fine to coarse angular to subrounded of sandstone																			
							1.50	Light brown gravelly clayey fine to coarse SAND. Gravel is fine to coarse angular to subrounded of sandstone																			
	2.00	D, ES						Light brown gravelly slightly clayey fine to coarse SAND with low cobble content. Gravel is fine to coarse angular to subrounded of sandstone. Cobbles are angular and subangular of sandstone																			
	3.00	D, ES, LB					3.10	END OF BOREHOLE							Dry		3.10										
Remarks: Trial pit CAT scanned prior to excavation to check for services. Ground-water was not encountered. The walls of the pit collapsed throughout excavation - sidewalls collapsed. Trial pit terminated at a depth of 3.10m due to sidewall collapse.																											
Driller		Originator RJB		Ground-water				Water Added		Chiselling			Flush				Fig No: B30 Sheet 1 of 1 Scale 1:50										
				Struck	Rose To	Time(min)	Cut Off	From	To	From	To	hh:mm	Returns	Type	From (m)	To (m)											
Chk & App FMR		Status Final																									

Style: BOREHOLE NEW File: P:\GINTWP\PROJECTS\26762.GPJ-44 (0)1698 710999 Printed: 13/12/2024 10:03:04 Raeburn Drilling and Geotechnical trading as IGNE, Whistleberry Rd, Hamilton ML3 0HP Tel: 01698-711177 E-mail: enquiries.raeburndrilling@igne.com



Remarks: Trial pit CAT scanned prior to excavation to check for services. Ground-water was not encountered. The walls of the pit collapsed throughout excavation - sidewalls collapsed. Trial pit terminated at a depth of 3.00m due to sidewall collapse.	To Depth	
	Hole Diam.	Boring Casing

Style: BOREHOLE NEW File: P:\GINTWP\PROJECTS\26762.GPJ+44 (0) 1698 710999 Printed: 13/12/2024 10:03:07 Raeburn Drilling and Geotechnical trading as (IGNE, Whistleberry Rd, Hamilton ML3 0HP Tel: 01698-711177 E-mail: enquiries.raeburndrilling@igne.com



Site: CAMBUSHINNIE 400KV SUBSTATION

Contract No: 26762

Client: Balfour Beatty
Engineer: Balfour Beatty

Borehole No.
BH01



Style: CORE PHOTOS File: P:\GINTWP\PROJECTS\26762.GPJ Printed: 12/12/2024 11:04:26 Raeburn Drilling and Geotechnical, Whistleberry Rd, Hamilton ML3 0HP Tel: 01698-711177 E-mail: enquiries@raeburndrilling.com

	Originator RB	Title: PHOTOGRAPHS OF ROCK CORE		Fig No: B32
Chk & App CJH	Status Final			



Site: CAMBUSHINNIE 400KV SUBSTATION

Contract No: 26762

Client: Balfour Beatty
Engineer: Balfour Beatty

Borehole No.
BH02



Style: CORE PHOTOS File: P:\GINTWP\PROJECTS\26762.GPJ Printed: 12/12/2024 11:04:30 Raeburn Drilling and Geotechnical, Whistleberry Rd, Hamilton ML3 0HP Tel: 01698-711177 E-mail: enquiries@raeburndrilling.com

	Originator RB	Title: PHOTOGRAPHS OF ROCK CORE		Fig No: B33
Chk & App CJH	Status Final			



Site: CAMBUSHINNIE 400KV SUBSTATION

Contract No: 26762

Client: Balfour Beatty

Engineer: Balfour Beatty

Borehole No.
PC01



Style: CORE PHOTOS File: P:\GINTWP\PROJECTS\26762.GPJ Printed: 12/12/2024 15:58:54 Raeburn Drilling and Geotechnical, Whistleberry Rd, Hamilton ML3 0HP Tel: 01698-711177 E-mail: enquiries@raeburndrilling.com

Originator

CB

Title:

PHOTOGRAPHS OF PAVEMENT CORES

Fig No:

B34

Chk & App

Status

CJH

Final




Site: CAMBUSHINNIE 400KV SUBSTATION

Contract No: 26762

Client: Balfour Beatty

Engineer: Balfour Beatty

Borehole No.
PC02



Originator

CB

Title:

PHOTOGRAPHS OF PAVEMENT CORES

Fig No:

B35

Chk & App

CJH

Status

Final




Site: CAMBUSHINNIE 400KV SUBSTATION

Contract No: 26762

Client: Balfour Beatty

Engineer: Balfour Beatty

Borehole No.
PC03



Originator

CB

Title:

PHOTOGRAPHS OF PAVEMENT CORES

Fig No:

B36

Chk & App

Status

CJH

Final



Site: CAMBUSHINNIE 400KV SUBSTATION

Contract No: 26762

Client: Balfour Beatty

Engineer: Balfour Beatty

Borehole No.
PC04



Originator

CB

Title:

PHOTOGRAPHS OF PAVEMENT CORES

Fig No:

B37

Chk & App

Status

CJH

Final



Site: CAMBUSHINNIE 400KV SUBSTATION

Contract No: 26762

Client: Balfour Beatty

Engineer: Balfour Beatty

Trial Pit No.

TP01



Originator

RB

Title:

PHOTOGRAPHS OF TRIAL PITS

Fig No:

B38

Chk & App

Status

CJH

Final



Site: CAMBUSHINNIE 400KV SUBSTATION

Contract No: 26762

Client: Balfour Beatty

Engineer: Balfour Beatty

Trial Pit No.
TP01



Originator

RB

Title:

PHOTOGRAPHS OF TRIAL PITS

Fig No:

B39

Chk & App

CJH

Status

Final





Site: CAMBUSHINNIE 400KV SUBSTATION

Contract No: 26762

Client: Balfour Beatty

Engineer: Balfour Beatty

Trial Pit No.

TP02



Originator

RB

Title:

PHOTOGRAPHS OF TRIAL PITS

Fig No:

B40

Chk & App

CJH

Status

Final



Site: CAMBUSHINNIE 400KV SUBSTATION

Contract No: 26762

Client: Balfour Beatty

Engineer: Balfour Beatty

Trial Pit No.
TP02



Style: TP PHOTOS File: P:\GINTW\PROJECTS\26762.GPJ Printed: 12/12/2024 11:05:56 Raeburn Drilling and Geotechnical, Whistleberry Rd, Hamilton ML3 0HP Tel: 01698-711177 E-mail: enquiries@raeburndrilling.com

Originator

RB

Title:

PHOTOGRAPHS OF TRIAL PITS

Fig No:

B41

Chk & App

CJH

Status

Final





Site: CAMBUSHINNIE 400KV SUBSTATION

Contract No: 26762

Client: Balfour Beatty

Engineer: Balfour Beatty

Trial Pit No.

TP03



Originator

RB

Title:

PHOTOGRAPHS OF TRIAL PITS

Fig No:

B42

Chk & App

Status

CJH

Final



Site: CAMBUSHINNIE 400KV SUBSTATION

Contract No: 26762

Client: Balfour Beatty

Engineer: Balfour Beatty

Trial Pit No.
TP03



Style: TP PHOTOS File: P:\GINTWP\PROJECTS\26762.GPJ Printed: 12/12/2024 11:06:05 Raeburn Drilling and Geotechnical, Whistleberry Rd, Hamilton ML3 0HP Tel: 01698-711177 E-mail: enquiries@raeburndrilling.com

Originator

RB

Title:

PHOTOGRAPHS OF TRIAL PITS

Fig No:

B43

Chk & App

Status

CJH

Final



Site: CAMBUSHINNIE 400KV SUBSTATION

Contract No: 26762

Client: Balfour Beatty

Engineer: Balfour Beatty

Trial Pit No.

TP04



Originator

RB

Title:

PHOTOGRAPHS OF TRIAL PITS

Fig No:

B44

Chk & App

Status

CJH

Final



Site: CAMBUSHINNIE 400KV SUBSTATION

Contract No: 26762

Client: Balfour Beatty

Engineer: Balfour Beatty

Trial Pit No.
TP04



Style: TP PHOTOS File: P:\GINTW\PROJECTS\26762.GPJ Printed: 12/12/2024 11:06:14 Raeburn Drilling and Geotechnical, Whistleberry Rd, Hamilton ML3 0HP Tel: 01698-711177 E-mail: enquiries@raeburndrilling.com

Originator

RB

Title:

PHOTOGRAPHS OF TRIAL PITS

Fig No:



B45

Chk & App

CJH

Status

Final



Site: CAMBUSHINNIE 400KV SUBSTATION

Contract No: 26762

Client: Balfour Beatty

Engineer: Balfour Beatty

Trial Pit No.

TP05



Originator

RB

Title:

PHOTOGRAPHS OF TRIAL PITS

Fig No:

B46

Chk & App

Status

CJH

Final



Site: CAMBUSHINNIE 400KV SUBSTATION

Contract No: 26762

Client: Balfour Beatty

Engineer: Balfour Beatty

Trial Pit No.
TP05



Style: TP PHOTOS File: P:\GINTW\PROJECTS\26762.GPJ Printed: 12/12/2024 11:06:24 Raeburn Drilling and Geotechnical, Whistleberry Rd, Hamilton ML3 0HP Tel: 01698-711177 E-mail: enquiries@raeburndrilling.com

Originator

RB

Title:

PHOTOGRAPHS OF TRIAL PITS

Fig No:

B47

Chk & App

CJH

Status

Final





Site: CAMBUSHINNIE 400KV SUBSTATION

Contract No: 26762

Client: Balfour Beatty

Engineer: Balfour Beatty

Trial Pit No.

TP06



Style: TP PHOTOS File: P:\GINTW\PROJECTS\26762.GPJ Printed: 13/12/2024 14:58:07 Raeburn Drilling and Geotechnical, Whistleberry Rd, Hamilton ML3 0HP Tel: 01698-711177 E-mail: enquiries@raeburndrilling.com

Originator

RB

Title:

PHOTOGRAPHS OF TRIAL PITS

Fig No:

B48

Chk & App

Status

CJH

Final



Site: CAMBUSHINNIE 400KV SUBSTATION

Contract No: 26762

Client: Balfour Beatty

Engineer: Balfour Beatty

Trial Pit No.

TP06



Style: TP PHOTOS File: P:\GINTW\PROJECTS\26762.GPJ Printed: 13/12/2024 14:58:07 Raeburn Drilling and Geotechnical, Whistleberry Rd, Hamilton ML3 0HP Tel: 01698-711177 E-mail: enquiries@raeburndrilling.com

Originator

RB

Title:

PHOTOGRAPHS OF TRIAL PITS

Fig No:

B49

Chk & App

CJH

Status

Final





Site: CAMBUSHINNIE 400KV SUBSTATION

Contract No: 26762

Client: Balfour Beatty

Engineer: Balfour Beatty

Trial Pit No.

TP07



Originator

RB

Title:

PHOTOGRAPHS OF TRIAL PITS

Fig No:

B50

Chk & App

CJH

Status

Final





Site: CAMBUSHINNIE 400KV SUBSTATION

Contract No: 26762

Client: Balfour Beatty

Engineer: Balfour Beatty

Trial Pit No.
TP07



Style: TP PHOTOS File: P:\GINTW\PROJECTS\26762.GPJ Printed: 13/12/2024 14:58:26 Raeburn Drilling and Geotechnical, Whistleberry Rd, Hamilton ML3 0HP Tel: 01698-711177 E-mail: enquiries@raeburndrilling.com

Originator

RB

Title:

PHOTOGRAPHS OF TRIAL PITS

Fig No:

B51

Chk & App

Status

CJH

Final



Site: CAMBUSHINNIE 400KV SUBSTATION

Contract No: 26762

Client: Balfour Beatty
Engineer: Balfour Beatty

Trial Pit No.
TP08



	Originator
	RB
Chk & App	Status
CJH	Final

Title:
PHOTOGRAPHS OF TRIAL PITS

Fig No:
B52



Site: CAMBUSHINNIE 400KV SUBSTATION

Contract No: 26762

Client: Balfour Beatty

Engineer: Balfour Beatty

Trial Pit No.
TP08



Style: TP PHOTOS File: P:\GINTW\PROJECTS\26762.GPJ Printed: 13/12/2024 14:58:34 Raeburn Drilling and Geotechnical, Whistleberry Rd, Hamilton ML3 0HP Tel: 01698-711177 E-mail: enquiries@raeburndrilling.com

Originator

RB

Title:

PHOTOGRAPHS OF TRIAL PITS

Fig No:

B53

Chk & App

Status

CJH

Final



Site: CAMBUSHINNIE 400KV SUBSTATION

Contract No: 26762

Client: Balfour Beatty

Engineer: Balfour Beatty

Trial Pit No.

TP09



Originator

RB

Title:

PHOTOGRAPHS OF TRIAL PITS

Fig No:

B54

Chk & App

CJH

Status

Final





Site: CAMBUSHINNIE 400KV SUBSTATION

Contract No: 26762

Client: Balfour Beatty

Engineer: Balfour Beatty

Trial Pit No.
TP09



Style: TP PHOTOS File: P:\GINTW\PROJECTS\26762.GPJ Printed: 13/12/2024 14:58:51 Raeburn Drilling and Geotechnical, Whistleberry Rd, Hamilton ML3 0HP Tel: 01698-711177 E-mail: enquiries@raeburndrilling.com

Originator

RB

Title:

PHOTOGRAPHS OF TRIAL PITS

Fig No:

B55

Chk & App

CJH

Status

Final





Site: CAMBUSHINNIE 400KV SUBSTATION


Contract No: 26762

Client: Balfour Beatty

Engineer: Balfour Beatty

Trial Pit No.

TP10



Originator

RB

Title:

PHOTOGRAPHS OF TRIAL PITS

Fig No:

B56

Chk & App

CJH

Status

Final





Site: CAMBUSHINNIE 400KV SUBSTATION

Contract No: 26762

Client: Balfour Beatty

Engineer: Balfour Beatty

Trial Pit No.
TP10



Style: TP PHOTOS File: P:\GINTW\PROJECTS\26762.GPJ Printed: 12/12/2024 14:09:22 Raeburn Drilling and Geotechnical, Whistleberry Rd, Hamilton ML3 0HP Tel: 01698-711177 E-mail: enquiries@raeburndrilling.com

Originator

RB

Title:

PHOTOGRAPHS OF TRIAL PITS

Fig No:



B57

Chk & App

CJH

Status

Final



Site: CAMBUSHINNIE 400KV SUBSTATION

Contract No: 26762

Client: Balfour Beatty

Engineer: Balfour Beatty

Trial Pit No.

TP11



Originator

RB

Title:

PHOTOGRAPHS OF TRIAL PITS

Fig No:

B58

Chk & App

Status

CJH

Final



Site: CAMBUSHINNIE 400KV SUBSTATION

Contract No: 26762

Client: Balfour Beatty

Engineer: Balfour Beatty

Trial Pit No.
TP11



Style: TP PHOTOS File: P:\GINTW\PROJECTS\26762.GPJ Printed: 12/12/2024 14:09:35 Raeburn Drilling and Geotechnical, Whistleberry Rd, Hamilton ML3 0HP Tel: 01698-711177 E-mail: enquiries@raeburndrilling.com

Originator

RB

Title:

PHOTOGRAPHS OF TRIAL PITS

Fig No:

B59

Chk & App

CJH

Status

Final





Site: CAMBUSHINNIE 400KV SUBSTATION

Contract No: 26762

Client: Balfour Beatty

Engineer: Balfour Beatty

Trial Pit No.

TP12



Originator

RB

Title:

PHOTOGRAPHS OF TRIAL PITS

Fig No:

B60

Chk & App

Status

CJH

Final



Site: CAMBUSHINNIE 400KV SUBSTATION

Contract No: 26762

Client: Balfour Beatty

Engineer: Balfour Beatty

Trial Pit No.
TP12



Style: TP PHOTOS File: P:\GINTW\PROJECTS\26762.GPJ Printed: 12/12/2024 14:09:46 Raeburn Drilling and Geotechnical, Whistleberry Rd, Hamilton ML3 0HP Tel: 01698-711177 E-mail: enquiries@raeburndrilling.com

Originator

RB

Title:

PHOTOGRAPHS OF TRIAL PITS

Fig No:

B61

Chk & App

CJH

Status

Final





Site: CAMBUSHINNIE 400KV SUBSTATION

Contract No: 26762

Client: Balfour Beatty

Engineer: Balfour Beatty

Trial Pit No.

TP13



Originator

RB

Title:

PHOTOGRAPHS OF TRIAL PITS

Fig No:

B62

Chk & App

CJH

Status

Final



Site: CAMBUSHINNIE 400KV SUBSTATION

Contract No: 26762

Client: Balfour Beatty

Engineer: Balfour Beatty

Trial Pit No.
TP13



Originator

RB

Title:

PHOTOGRAPHS OF TRIAL PITS

Fig No:

B63

Chk & App

CJH

Status

Final



Originator

RB

Title:

PHOTOGRAPHS OF TRIAL PITS

Fig No:

B64

Chk & App

CJH

Status

Final



Site: CAMBUSHINNIE 400KV SUBSTATION

Contract No: 26762

Client: Balfour Beatty

Engineer: Balfour Beatty

Trial Pit No.
TP14



Style: TP PHOTOS File: P:\GINTW\PROJECTS\26762.GPJ Printed: 12/12/2024 14:10:05 Raeburn Drilling and Geotechnical, Whistleberry Rd, Hamilton ML3 0HP Tel: 01698-711177 E-mail: enquiries@raeburndrilling.com

Originator

RB

Title:

PHOTOGRAPHS OF TRIAL PITS

Fig No:

B65

Chk & App

CJH

Status

Final





Site: CAMBUSHINNIE 400KV SUBSTATION

Contract No: 26762

Client: Balfour Beatty

Engineer: Balfour Beatty

Trial Pit No.

TP15



Originator

RB

Title:

PHOTOGRAPHS OF TRIAL PITS

Fig No:

B66

Chk & App

CJH

Status

Final





Site: CAMBUSHINNIE 400KV SUBSTATION

Contract No: 26762

Client: Balfour Beatty

Engineer: Balfour Beatty

Trial Pit No.
TP15



Style: TP PHOTOS File: P:\GINTW\PROJECTS\26762.GPJ Printed: 12/12/2024 14:10:15 Raeburn Drilling and Geotechnical, Whistleberry Rd, Hamilton ML3 0HP Tel: 01698-711177 E-mail: enquiries@raeburndrilling.com

Originator

RB

Title:

PHOTOGRAPHS OF TRIAL PITS

Fig No:

B67

Chk & App

CJH

Status

Final





Site: CAMBUSHINNIE 400KV SUBSTATION

Contract No: 26762

Client: Balfour Beatty

Engineer: Balfour Beatty

Trial Pit No.

TP16



Originator

RB

Title:

PHOTOGRAPHS OF TRIAL PITS

Fig No:

B68

Chk & App

CJH

Status

Final



Site: CAMBUSHINNIE 400KV SUBSTATION

Contract No: 26762

Client: Balfour Beatty

Engineer: Balfour Beatty

Trial Pit No.

TP16



Originator

RB

Title:

PHOTOGRAPHS OF TRIAL PITS

Fig No:

B69

Chk & App

CJH

Status

Final



Site: CAMBUSHINNIE 400KV SUBSTATION

Contract No: 26762

Client: Balfour Beatty

Engineer: Balfour Beatty

Trial Pit No.

TP17



Originator

RB

Title:

PHOTOGRAPHS OF TRIAL PITS

Fig No:

B70

Chk & App

Status

CJH

Final



Site: CAMBUSHINNIE 400KV SUBSTATION

Contract No: 26762

Client: Balfour Beatty

Engineer: Balfour Beatty

Trial Pit No.
TP17



Originator

RB

Title:

PHOTOGRAPHS OF TRIAL PITS

Fig No:

B71

Chk & App

CJH

Status

Final





Site: CAMBUSHINNIE 400KV SUBSTATION

Contract No: 26762

Client: Balfour Beatty

Engineer: Balfour Beatty

Trial Pit No.

TP18



Originator

RB

Title:

PHOTOGRAPHS OF TRIAL PITS

Fig No:

B72

Chk & App

Status

CJH

Final



Site: CAMBUSHINNIE 400KV SUBSTATION

Contract No: 26762

Client: Balfour Beatty

Engineer: Balfour Beatty

Trial Pit No.
TP18



Style: TP PHOTOS File: P:\GINTW\PROJECTS\26762.GPJ Printed: 12/12/2024 14:13:13 Raeburn Drilling and Geotechnical, Whistleberry Rd, Hamilton ML3 0HP Tel: 01698-711177 E-mail: enquiries@raeburndrilling.com

Originator

RB

Title:

PHOTOGRAPHS OF TRIAL PITS

Fig No:

B73

Chk & App

Status

CJH

Final



Site: CAMBUSHINNIE 400KV SUBSTATION

Contract No: 26762

Client: Balfour Beatty

Engineer: Balfour Beatty

Trial Pit No.

TP19



Originator

RB

Title:

PHOTOGRAPHS OF TRIAL PITS

Fig No:

B74

Chk & App

Status

CJH

Final



Site: CAMBUSHINNIE 400KV SUBSTATION

Contract No: 26762

Client: Balfour Beatty

Engineer: Balfour Beatty

Trial Pit No.
TP19



Style: TP PHOTOS File: P:\GINTW\PROJECTS\26762.GPJ Printed: 12/12/2024 14:13:21 Raeburn Drilling and Geotechnical, Whistleberry Rd, Hamilton ML3 0HP Tel: 01698-711177 E-mail: enquiries@raeburndrilling.com

Originator

RB

Title:

PHOTOGRAPHS OF TRIAL PITS

Fig No:

B75

Chk & App

Status

CJH

Final



Site: CAMBUSHINNIE 400KV SUBSTATION

Contract No: 26762

Client: Balfour Beatty

Engineer: Balfour Beatty

Trial Pit No.

TP20



Originator

RB

Title:

PHOTOGRAPHS OF TRIAL PITS

Fig No:

B76

Chk & App

Status

CJH

Final



Site: CAMBUSHINNIE 400KV SUBSTATION

Contract No: 26762

Client: Balfour Beatty

Engineer: Balfour Beatty

Trial Pit No.
TP20



Style: TP PHOTOS File: P:\GINTW\PROJECTS\26762.GPJ Printed: 12/12/2024 14:13:31 Raeburn Drilling and Geotechnical, Whistleberry Rd, Hamilton ML3 0HP Tel: 01698-711177 E-mail: enquiries@raeburndrilling.com

Originator

RB

Title:

PHOTOGRAPHS OF TRIAL PITS

Fig No:

B77

Chk & App

CJH

Status

Final





Site: CAMBUSHINNIE 400KV SUBSTATION

Contract No: 26762

Client: Balfour Beatty

Engineer: Balfour Beatty

Trial Pit No.

TP21



Originator

RB

Title:

PHOTOGRAPHS OF TRIAL PITS

Fig No:

B78

Chk & App

CJH

Status

Final



Site: CAMBUSHINNIE 400KV SUBSTATION

Contract No: 26762

Client: Balfour Beatty

Engineer: Balfour Beatty

Trial Pit No.
TP21



Style: TP PHOTOS File: P:\GINTW\PROJECTS\26762.GPJ Printed: 12/12/2024 14:15:05 Raeburn Drilling and Geotechnical, Whistleberry Rd, Hamilton ML3 0HP Tel: 01698-711177 E-mail: enquiries@raeburndrilling.com

Originator

RB

Title:

PHOTOGRAPHS OF TRIAL PITS

Fig No:

B79

Chk & App

CJH

Status

Final



Site: CAMBUSHINNIE 400KV SUBSTATION

Contract No: 26762

Client: Balfour Beatty

Engineer: Balfour Beatty

Trial Pit No.

TP22



Originator

RB

Title:

PHOTOGRAPHS OF TRIAL PITS

Fig No:

B80

Chk & App

CJH

Status

Final





Site: CAMBUSHINNIE 400KV SUBSTATION

Contract No: 26762

Client: Balfour Beatty

Engineer: Balfour Beatty

Trial Pit No.
TP22



Style: TP PHOTOS File: P:\GINTW\PROJECTS\26762.GPJ Printed: 12/12/2024 14:15:12 Raeburn Drilling and Geotechnical, Whistleberry Rd, Hamilton ML3 0HP Tel: 01698-711177 E-mail: enquiries@raeburndrilling.com

Originator

RB

Title:

PHOTOGRAPHS OF TRIAL PITS

Fig No:

B81

Chk & App

CJH

Status

Final



Site: CAMBUSHINNIE 400KV SUBSTATION

Contract No: 26762

Client: Balfour Beatty

Engineer: Balfour Beatty

**SPT Hammer Energy Test Report**

in accordance with BSEN ISO 22476-3:2005

**Whistleberry Road
Hamilton
ML3 OHP**

SPT Hammer Ref: RD53 2024

Test Date: 05/02/2024

Report Date: 05/02/2024

File Name: RD53 2024.spt





Test Operator: KS

Instrumented Rod Data

Diameter d_r (mm): 54
Wall Thickness t_r (mm): 6.6
Assumed Modulus E_a (GPa): 208
Accelerometer No.1: 69559
Accelerometer No.2: 69560

SPT Hammer Information

Hammer Mass m (kg): 63.5
Falling Height h (mm): 760
SPT String Length L (m): 14.5

Comments / Location**Calculations**

Area of Rod A (mm^2): 983
Theoretical Energy E_{theor} (J): 473
Measured Energy E_{meas} (J): 339

Energy Ratio E_r (%): **72**

Signed: Kevin Steele

Title: Drilling Store Manager

The recommended calibration interval is 12 months

SPTMAN ver.1.92 All rights reserved, Testconsult ©2010

Originator

RB

Title:

SPT HAMMER ENERGY REPORT - RD53

Fig No:

B82

Chk & App

CJH

Status

Final



SPT Hammer Energy Test Report

in accordance with BSEN ISO 22476-3:2005

**Whistleberry Road
Hamilton
ML3 0HP**

SPT Hammer Ref: TER22 2024

Test Date: 12/06/2024

Report Date: 12/06/2024

File Name: TER22 2024.spt

Test Operator: KS





Instrumented Rod Data

Diameter d_r (mm): 54
Wall Thickness t_r (mm): 6.8
Assumed Modulus E_a (GPa): 208
Accelerometer No.1: 69559
Accelerometer No.2: 69560

SPT Hammer Information

Hammer Mass m (kg): 63.5
Falling Height h (mm): 760
SPT String Length L (m): 14.5

Comments / Location



Calculations

Area of Rod A (mm^2): 1008
Theoretical Energy E_{theor} (J): 473
Measured Energy E_{meas} (J): 348

Energy Ratio E_r (%): **73**

Signed: Kevin Steele

Title: Drilling Store Manager

The recommended calibration interval is 12 months

SPTMAN ver.1.92 All rights reserved, Testconsult ©2010



Site

CAMBUSHINNIE HAUL ROAD

Contract No 26762

Client

Balfour Beatty

Engineer

WSP

Date tested 23/10/2024

Test Location ~

Tested by JW


DCP No. 1

Weather Variable

Zero Error (mm) 11

DYNAMIC CONE PENETROMETER GRAPH

Number of Blows



Start Depth (mm)	Finish Depth (mm)	No. of Blows	Blows per Layer	Material	DCP mm/blow	Estimated average CBR over depth range (%)
11	100	1	1	Unknown	89.00	3
100	900	88	87	Unknown	9.20	29
900	901	128	40	Unknown	0.03	14907

Remarks:

Cone Angle 60°

UKAS accredited test - No

Test abandoned due to refusal of test equipment; less than 4mm penetration in 40 blows

Originator

Checked & Approved

Dynamic Cone Penetrometer

CL

CD
13/12/2024

In-house procedure TP166 with reference to CS 229 cl 6 of the DMRB

B84

Sheet 1 of 1



Site

CAMBUSHINNIE HAUL ROAD

Contract No 26762

Client

Balfour Beatty

Engineer

WSP

Date tested 22/10/2024

Test Location ~

Tested by JW


DCP No. 2

Weather Variable

Zero Error (mm) 24

DYNAMIC CONE PENETROMETER GRAPH

Number of Blows



Start Depth (mm)	Finish Depth (mm)	No. of Blows	Blows per Layer	Material	DCP mm/blow	Estimated average CBR over depth range (%)
22	200	4	4	Unknown	44.50	5
200	600	47	43	Unknown	9.30	29
600	601	87	40	Unknown	0.03	14907

Remarks:

Cone Angle 60°

UKAS accredited test - No

Test abandoned due to refusal of test equipment; less than 4mm penetration in 40 blows

Originator

Checked & Approved

Dynamic Cone Penetrometer

CL

CD
13/12/2024

In-house procedure TP166 with reference to CS 229 cl 6 of the DMRB


B85

Sheet 1 of 1



Site	CAMBUSHINNIE HAUL ROAD	Contract No 26762
Client	Balfour Beatty	
Engineer	WSP	

Date tested	22/10/2024	Test Location	~
Tested by	JW	DCP No.	3
Weather	Variable	Zero Error (mm)	32



Start Depth (mm)	Finish Depth (mm)	No. of Blows	Blows per Layer	Material	DCP mm/blow	Estimated average CBR over depth range (%)
32	300	3	3	Unknown	89.33	3
300	700	18	15	Unknown	26.67	9
700	1000	67	49	Unknown	6.12	44
1000	1003	107	40	Unknown	0.08	4667

Remarks:


Cone Angle 60°
UKAS accredited test - No
Test abandoned due to refusal of test equipment; less than 4mm penetration in 40 blows

Originator	Checked & Approved	Dynamic Cone Penetrometer	
CL	CD 13/12/2024	In-house procedure TP166 with reference to CS 229 cl 6 of the DMRB	
		B86 Sheet 1 of 1	



Site CAMBUSHINNIE HAUL ROAD		Contract No 26762
Client	Balfour Beatty	
Engineer	WSP	

Date tested	22/10/2024	Test Location	~
Tested by	JW	DCP No.	4
Weather	Variable	Zero Error (mm)	29



Start Depth (mm)	Finish Depth (mm)	No. of Blows	Blows per Layer	Material	DCP mm/blow	Estimated average CBR over depth range (%)
29	400	5	5	Unknown	74.20	3
400	900	34	29	Unknown	17.24	15
900	1100	74	40	Unknown	5.00	55
1100	1500	108	34	Unknown	11.76	22


Remarks:
Cone Angle 60°
UKAS accredited test - No

Originator	Checked & Approved	Dynamic Cone Penetrometer	B87 Sheet 1 of 1
CL	CD 13/12/2024	In-house procedure TP166 with reference to CS 229 cl 6 of the DMRB	



Site	CAMBUSHINNIE HAUL ROAD	Contract No 26762
Client	Balfour Beatty	
Engineer	WSP	

Date tested	22/10/2024	Test Location	~
Tested by	JW	DCP No.	4
Weather	Variable	Zero Error (mm)	32



Start Depth (mm)	Finish Depth (mm)	No. of Blows	Blows per Layer	Material	DCP mm/blow	Estimated average CBR over depth range (%)
32	400	6	6	Unknown	61.33	4
400	800	25	19	Unknown	21.05	12
800	1100	66	41	Unknown	7.32	37
1100	1500	124	58	Unknown	6.90	39


Remarks:
Cone Angle 60°
UKAS accredited test - No

Originator	Checked & Approved	Dynamic Cone Penetrometer	
CL	CD 13/12/2024	In-house procedure TP166 with reference to CS 229 cl 6 of the DMRB	
		B88 Sheet 1 of 1	



Site	CAMBUSHINNIE HAUL ROAD	Contract No 26762
Client	Balfour Beatty	
Engineer	WSP	

Date tested	16/10/2024	Test Location	~
Tested by	JD	DCP No.	6
Weather	Variable	Zero Error (mm)	56



Start Depth (mm)	Finish Depth (mm)	No. of Blows	Blows per Layer	Material	DCP mm/blow	Estimated average CBR over depth range (%)
56	329	21	21	Unknown	13.00	20
329	461	46	25	Unknown	5.28	52
461	710	126	70	Unknown	3.56	79
710	1500	287	161	Unknown	4.91	56

Remarks:
Cone Angle 60°
UKAS accredited test - No

Originator	Checked & Approved	Dynamic Cone Penetrometer	B89 Sheet 1 of 1
CL	CD 13/12/2024	In-house procedure TP166 with reference to CS 229 cl 6 of the DMRB	



Site

CAMBUSHINNIE HAUL ROAD

Contract No 26762

Client

Balfour Beatty

Engineer

WSP

Date tested 16/10/2024


Test Location ~

Tested by JD

DCP No. 7

Weather Variable

Zero Error (mm) 36



Start Depth (mm)	Finish Depth (mm)	No. of Blows	Blows per Layer	Material	DCP mm/blow	Estimated average CBR over depth range (%)
36	627	11	11	Unknown	53.73	4
627	892	34	23	Unknown	11.52	23
892	1242	99	65	Unknown	5.38	51
1242	1500	179	80	Unknown	3.23	88

Remarks:

Cone Angle 60°

UKAS accredited test - No

Originator

Checked & Approved

Dynamic Cone Penetrometer

CL

CD
13/12/2024

In-house procedure TP166 with reference to CS 229 cl 6 of the DMRB


B90

Sheet 1 of 1



Site	CAMBUSHINNIE HAUL ROAD	Contract No 26762
Client	Balfour Beatty	
Engineer	WSP	

Date tested	15/10/2024	Test Location	~
Tested by	JD	DCP No.	8
Weather	Variable	Zero Error (mm)	56



Start Depth (mm)	Finish Depth (mm)	No. of Blows	Blows per Layer	Material	DCP mm/blow	Estimated average CBR over depth range (%)
56	760	29	29	Unknown	24.28	10
760	972	94	65	Unknown	3.26	87
972	1126	119	25	Unknown	6.16	44
1126	1128	159	40	Unknown	0.05	7165

Remarks:

Cone Angle 60°
UKAS accredited test - No
Test abandoned due to refusal of test equipment; less than 4mm penetration in 40 blows

Originator	Checked & Approved	Dynamic Cone Penetrometer	B91 Sheet 1 of 1
CL	CD 13/12/2024	In-house procedure TP166 with reference to CS 229 cl 6 of the DMRB	



Site

CAMBUSHINNIE HAUL ROAD

Contract No 26762

Client

Balfour Beatty

Engineer

WSP

Date tested 16/10/2024


Test Location ~

Tested by JD

DCP No. 9

Weather Variable

Zero Error (mm) 50



Start Depth (mm)	Finish Depth (mm)	No. of Blows	Blows per Layer	Material	DCP mm/blow	Estimated average CBR over depth range (%)
50	1000	28	28	Unknown	33.93	7
1000	1115	48	20	Unknown	5.75	48
1115	1355	68	20	Unknown	12.00	22
1355	1500	95	27	Unknown	5.37	51

Remarks:

Cone Angle 60°

UKAS accredited test - No

Originator

Checked & Approved

Dynamic Cone Penetrometer

CL

CD
13/12/2024

In-house procedure TP166 with reference to CS 229 cl 6 of the DMRB


B92

Sheet 1 of 1



Site	CAMBUSHINNIE HAUL ROAD	Contract No 26762
Client	Balfour Beatty	
Engineer	WSP	

Date tested	16/10/2024	Test Location	~
Tested by	JD	DCP No.	10
Weather	Variable	Zero Error (mm)	40



Start Depth (mm)	Finish Depth (mm)	No. of Blows	Blows per Layer	Material	DCP mm/blow	Estimated average CBR over depth range (%)
40	396	8	8	Unknown	44.50	5
396	647	23	15	Unknown	16.73	15
647	1000	33	10	Unknown	35.30	7
1000	1254	48	15	Unknown	16.93	15
1254	1500	93	45	Unknown	5.47	50

Remarks:

Cone Angle 60°
UKAS accredited test - No

Originator	Checked & Approved	Dynamic Cone Penetrometer	B93 Sheet 1 of 1
CL	CD 13/12/2024	In-house procedure TP166 with reference to CS 229 cl 6 of the DMRB	



Site

CAMBUSHINNIE HAUL ROAD

Contract No 26762

Client

Balfour Beatty

Engineer

WSP

Date tested 17/10/2024


Test Location ~

Tested by JD

DCP No. 11

Weather Variable

Zero Error (mm) 130



Start Depth (mm)	Finish Depth (mm)	No. of Blows	Blows per Layer	Material	DCP mm/blow	Estimated average CBR over depth range (%)
130	415	4	4	Unknown	71.25	3
415	655	24	20	Unknown	12.00	22
655	810	49	25	Unknown	6.20	44
810	1000	69	20	Unknown	9.50	28
1000	1310	169	100	Unknown	3.10	91
1310	1500	197	28	Unknown	6.79	40

Remarks:

Cone Angle 60°

UKAS accredited test - No

Originator	Checked & Approved	Dynamic Cone Penetrometer	B94 Sheet 1 of 1
CL	CD 13/12/2024	In-house procedure TP166 with reference to CS 229 cl 6 of the DMRB	



Site

CAMBUSHINNIE HAUL ROAD

Contract No 26762

Client

Balfour Beatty

Engineer

WSP

Date tested 17/10/2024

Test Location ~

Tested by JD


DCP No. 12

Weather Variable

Zero Error (mm) 60

DYNAMIC CONE PENETROMETER GRAPH

Number of Blows



Start Depth (mm)	Finish Depth (mm)	No. of Blows	Blows per Layer	Material	DCP mm/blow	Estimated average CBR over depth range (%)
60	640	7	7	Unknown	82.86	3
640	850	18	11	Unknown	19.09	13
850	1000	40	22	Unknown	6.82	40
1000	1234	60	20	Unknown	11.70	22
1234	1500	117	57	Unknown	4.67	59

Remarks:

Cone Angle 60°

UKAS accredited test - No

Originator

Checked & Approved

Dynamic Cone Penetrometer

CL

CD
13/12/2024

In-house procedure TP166 with reference to CS 229 cl 6 of the DMRB

B95

Sheet 1 of 1



Site

CAMBUSHINNIE HAUL ROAD

Contract No 26762

Client

Balfour Beatty

Engineer

WSP

Date tested 23/10/2024

Test Location ~

Tested by JW


DCP No. 16

Weather Variable

Zero Error (mm) 10

DYNAMIC CONE PENETROMETER GRAPH

Number of Blows



Start Depth (mm)	Finish Depth (mm)	No. of Blows	Blows per Layer	Material	DCP mm/blow	Estimated average CBR over depth range (%)
100	500	9	9	Unknown	44.44	5
500	900	57	48	Unknown	8.33	32
900	902	97	40	Unknown	0.05	7165

Remarks:

Cone Angle 60°

UKAS accredited test - No

Test abandoned due to refusal of test equipment; less than 4mm penetration in 40 blows

Originator

Checked & Approved

Dynamic Cone Penetrometer

CL

CD
13/12/2024

In-house procedure TP166 with reference to CS 229 cl 6 of the DMRB


B96

Sheet 1 of 1



Site	CAMBUSHINNIE HAUL ROAD	Contract No 26762
Client	Balfour Beatty	
Engineer	WSP	

Date tested	23/10/2024	Test Location	~
Tested by	JW	DCP No.	17
Weather	Variable	Zero Error (mm)	20



Start Depth (mm)	Finish Depth (mm)	No. of Blows	Blows per Layer	Material	DCP mm/blow	Estimated average CBR over depth range (%)
100	300	3	3	Unknown	66.67	4
300	500	5	2	Unknown	100.00	2
500	800	16	11	Unknown	27.27	9
800	1500	89	73	Unknown	9.59	28


Remarks:
Cone Angle 60°
UKAS accredited test - No

Originator	Checked & Approved	Dynamic Cone Penetrometer	B97 Sheet 1 of 1
CL	CD 13/12/2024	In-house procedure TP166 with reference to CS 229 cl 6 of the DMRB	



Site	CAMBUSHINNIE HAUL ROAD	Contract No 26762
Client	Balfour Beatty	
Engineer	WSP	

Date tested	23/10/2024	Test Location	~
Tested by	JW	DCP No.	18
Weather	Variable	Zero Error (mm)	19



Start Depth (mm)	Finish Depth (mm)	No. of Blows	Blows per Layer	Material	DCP mm/blow	Estimated average CBR over depth range (%)
19	200	2	2	Unknown	90.50	3
200	800	6	4	Unknown	150.00	2
800	1200	34	28	Unknown	14.29	18
1200	1500	74	40	Unknown	7.50	36

Remarks:
Cone Angle 60°
UKAS accredited test - No

Originator	Checked & Approved	Dynamic Cone Penetrometer	B98 Sheet 1 of 1
CL	CD 13/12/2024	In-house procedure TP166 with reference to CS 229 cl 6 of the DMRB	



Site

CAMBUSHINNIE HAUL ROAD

Contract No 26762

Client

Balfour Beatty

Engineer

WSP

Date tested 17/10/2024


Test Location ~

Tested by JD

DCP No. 19

Weather Variable

Zero Error (mm) 76



Start Depth (mm)	Finish Depth (mm)	No. of Blows	Blows per Layer	Material	DCP mm/blow	Estimated average CBR over depth range (%)
76	1108	10	10	Unknown	103.20	2
1108	1232	14	4	Unknown	31.00	8
1232	1345	23	9	Unknown	12.56	21
1345	1500	65	42	Unknown	3.69	76

Remarks:

Cone Angle 60°

UKAS accredited test - No

Originator

Checked & Approved

Dynamic Cone Penetrometer

CL

CD
13/12/2024

In-house procedure TP166 with reference to CS 229 cl 6 of the DMRB


B99

Sheet 1 of 1



Site	CAMBUSHINNIE HAUL ROAD	Contract No 26762
Client	Balfour Beatty	
Engineer	WSP	

Date tested	17/10/2024	Test Location	~
Tested by	JD	DCP No.	20
Weather	Variable	Zero Error (mm)	160



Start Depth (mm)	Finish Depth (mm)	No. of Blows	Blows per Layer	Material	DCP mm/blow	Estimated average CBR over depth range (%)
160	284	1	1	Unknown	124.00	2
284	412	4	3	Unknown	42.67	6
412	1260	23	19	Unknown	44.63	5
1260	1500	48	25	Unknown	9.60	28


Remarks:
Cone Angle 60°
UKAS accredited test - No

Originator	Checked & Approved	Dynamic Cone Penetrometer	B100 Sheet 1 of 1
CL	CD 13/12/2024	In-house procedure TP166 with reference to CS 229 cl 6 of the DMRB	



Site	CAMBUSHINNIE HAUL ROAD	Contract No 26762
Client	Balfour Beatty	
Engineer	WSP	

Date tested	18/10/2024	Test Location	~
Tested by	JD	DCP No.	21
Weather	Variable	Zero Error (mm)	60




Start Depth (mm)	Finish Depth (mm)	No. of Blows	Blows per Layer	Material	DCP mm/blow	Estimated average CBR over depth range (%)
60	400	5	5	Unknown	68.00	3
400	689	37	32	Unknown	9.03	29
689	692	47	10	Unknown	0.30	1078
692	731	67	20	Unknown	1.95	149
731	733	107	40	Unknown	0.05	7165

Remarks:

Cone Angle 60°

UKAS accredited test - No


Test abandoned due to refusal of test equipment; less than 4mm penetration in 40 blows

Originator	Checked & Approved	Dynamic Cone Penetrometer	
CL	 13/12/2024	In-house procedure TP166 with reference to CS 229 cl 6 of the DMRB	
B101			Sheet 1 of 1



Site	CAMBUSHINNIE HAUL ROAD	Contract No 26762
Client	Balfour Beatty	
Engineer	WSP	

Date tested	17/10/2024	Test Location	~
Tested by	JD	DCP No.	22
Weather	Variable	Zero Error (mm)	45







Start Depth (mm)	Finish Depth (mm)	No. of Blows	Blows per Layer	Material	DCP mm/blow	Estimated average CBR over depth range (%)
45	610	6	6	Unknown	94.17	2
610	830	28	22	Unknown	10.00	26
830	1376	67	39	Unknown	14.00	19
1376	1500	72	5	Unknown	24.80	10

Remarks:

Cone Angle 60°
UKAS accredited test - No
Test abandoned due to refusal of test equipment; less than 4mm penetration in 40 blows

Originator	Checked & Approved	Dynamic Cone Penetrometer	
CL	CD 13/12/2024	In-house procedure TP166 with reference to CS 229 cl 6 of the DMRB	
			B102 Sheet 1 of 1

<div></div>				Site: CAMBUSHINNIE 400KV SUBSTATION									Contract No: 26762		
				Client: Balfour Beatty Engineer: Balfour Beatty									* Water level measurements taken from ground level.		
Borehole No.	Surveyed Level (m OD)	Depth to Base of Standpipe (m)	Date /Time	Atmospheric Pressure (mBar)	Gas Composition					Differential Pressure (Pa)	Flow (l/hr)	Depth to Water (m) (mBGL)	Depth (mAOD)	Remarks	
					CH ₄ (%vol)	CO ₂ (%vol)	O ₂ (%vol)	H ₂ S (ppm)	CO (ppm)						
BH01			21/11/24 11:34	983	0.00	0.20	20.20	0.00	1.00	0.00	0.00	3.30		Dry, hazy, cool	
			21/11/24 11:35		0.00	3.90	14.10	0.00	3.00					Dry, hazy, cool	
			21/11/24 11:36		0.00	4.00	13.40	0.00	1.00					Dry, hazy, cool	
			21/11/24 11:37		0.00	4.00	13.20	0.00	1.00					Dry, hazy, cool	
			21/11/24 11:38		0.00	4.10	13.10	0.00	5.00					Dry, hazy, cool	
			21/11/24 11:39		0.00	4.10	13.10	0.00	3.00					Dry, hazy, cool	
			03/12/24 13:24	1008	0.00	0.50	20.00	0.00	0.00	0.00	0.00	3.17		Dry, sunny, mild	
			03/12/24 13:25		0.00	3.70	15.80	0.00	0.00					Dry, sunny, mild	
			03/12/24 13:26		0.00	3.90	13.40	0.00	0.00					Dry, sunny, mild	
			03/12/24 13:27		0.00	3.90	13.00	0.00	1.00					Dry, sunny, mild	
			03/12/24 13:28		0.00	3.90	12.90	0.00	1.00					Dry, sunny, mild	
			03/12/24 13:29		0.00	3.90	12.90	0.00	0.00					Dry, sunny, mild	
			10/12/24 09:17	1028	0.00	0.00	20.00	0.00	3.00	0.00	0.00	2.83		Dry, sunny, cold	
			10/12/24 09:18		0.00	4.00	13.30	0.00	1.00					Dry, sunny, cold	
			10/12/24 09:19		0.00	4.10	12.30	0.00	0.00					Dry, sunny, cold	
		10/12/24 09:20		0.00	4.10	12.10	0.00	0.00					Dry, sunny, cold		
		10/12/24 09:21		0.00	4.10	12.10	0.00	0.00					Dry, sunny, cold		
		10/12/24 09:22		0.00	4.10	12.10	0.00	0.00					Dry, sunny, cold		
BH02			21/11/24 12:11	982	0.00	3.60	16.80	0.00	0.00	0.00	0.00	2.73		Dry, hazy, cool	
			21/11/24 12:12		0.00	2.10	18.40	0.00	0.00					Dry, hazy, cool	
			21/11/24 12:13		0.00	2.10	18.60	0.00	1.00					Dry, hazy, cool	
			21/11/24 12:14		0.00	2.10	18.60	0.00	0.00					Dry, hazy, cool	
			21/11/24 12:15		0.00	2.10	18.60	0.00	1.00					Dry, hazy, cool	
			21/11/24 12:16		0.00	2.10	18.70	0.00	1.00					Dry, hazy, cool	
			03/12/24 11:52	1008	0.00	0.00	19.80	0.00	0.00	0.00	0.00	2.45		Dry, sunny, mild	
			03/12/24 11:53		0.00	0.90	20.10	0.00	0.00					Dry, sunny, mild	
			03/12/24 11:54		0.00	2.20	19.00	0.00	0.00					Dry, sunny, mild	
			03/12/24 11:55		0.00	2.40	18.40	0.00	0.00					Dry, sunny, mild	
			03/12/24 11:56		0.00	2.60	18.20	0.00	0.00					Dry, sunny, mild	
			03/12/24 11:57		0.00	2.60	18.20	0.00	1.00					Dry, sunny, mild	
			10/12/24 10:45	1028	0.00	3.10	17.30	0.00	0.00	0.00	0.00	2.27		Dry, sunny, cold	
			10/12/24 10:46		0.00	1.90	17.70	0.00	0.00					Dry, sunny, cold	
			10/12/24 10:47		0.00	1.90	17.90	0.00	0.00					Dry, sunny, cold	
		10/12/24 10:48		0.00	1.90	17.90	0.00	0.00					Dry, sunny, cold		
		10/12/24 10:49		0.00	1.90	17.90	0.00	0.00					Dry, sunny, cold		
		10/12/24 10:50		0.00	1.90	17.90	0.00	0.00					Dry, sunny, cold		
WS01			21/11/24 12:28	982	0.00	2.00	18.40	0.00	0.00	0.00	0.00	1.99		Dry, hazy, cool	
			21/11/24 12:29		0.00	4.50	17.10	0.00	0.00					Dry, hazy, cool	
			21/11/24 12:30		0.00	4.50	16.90	0.00	0.00					Dry, hazy, cool	
			21/11/24 12:31		0.00	4.70	18.60	0.00	1.00					Dry, hazy, cool	
			21/11/24 12:32		0.00	4.80	16.80	0.00	0.00					Dry, hazy, cool	
			21/11/24 12:33		0.00	4.80	16.70	0.00	1.00					Dry, hazy, cool	
			03/12/24 00:00											No gas test possible as gas	
													valve removed		
Originator		Title: RESULTS OF GAS AND WATER LEVEL MONITORING IN STANDPIPES													Fig No: B103
JMcM															
Chk & App	Status														
CJH	Final														Sheet 1 of 3

<div></div>				Site: CAMBUSHINNIE 400KV SUBSTATION									Contract No: 26762				
				Client: Balfour Beatty Engineer: Balfour Beatty									Water level measurements taken from ground level.				
Borehole No.	Surveyed Level (m OD)	Depth to Base of Standpipe (m)	Date /Time	Atmospheric Pressure (mBar)	Gas Composition					Differential Pressure (Pa)	Flow (l/hr)	Depth to Water (m) (mBGL)	Depth (mAOD)	Remarks			
					CH ₄ (%vol)	CO ₂ (%vol)	O ₂ (%vol)	H ₂ S (ppm)	CO (ppm)								
WS01			03/12/24 00:00									1.19		Dry, sunny, mild			
			10/12/24 11:10	1027	0.00	1.90	17.90	0.00	0.00	0.00	0.00	0.76		Dry, sunny, cold			
			10/12/24 11:11		0.00	3.30	17.20	0.00	0.00					Dry, sunny, cold			
			10/12/24 11:12		0.00	3.30	17.20	0.00	0.00					Dry, sunny, cold			
			10/12/24 11:13		0.00	3.30	17.10	0.00	0.00					Dry, sunny, cold			
			10/12/24 11:14		0.00	3.30	17.10	0.00	0.00					Dry, sunny, cold			
			10/12/24 11:15		0.00	3.30	17.10	0.00	0.00					Dry, sunny, cold			
WS02			21/11/24 12:45	982	0.00	4.30	17.50	0.00	0.00	0.00	0.00	0.91		Dry, hazy, cool			
			21/11/24 12:46		0.00	6.20	16.20	0.00	0.00					Dry, hazy, cool			
			21/11/24 12:47		0.00	6.20	16.20	0.00	0.00					Dry, hazy, cool			
			21/11/24 12:48		0.00	6.20	16.20	0.00	0.00					Dry, hazy, cool			
			21/11/24 12:49		0.00	6.30	16.10	0.00	0.00					Dry, hazy, cool			
			21/11/24 12:50		0.00	6.30	16.10	0.00	0.00					Dry, hazy, cool			
			03/12/24 12:16	1008	0.00	0.50	19.90	0.00	0.00	0.00	0.00	0.35		Dry, sunny, mild			
			03/12/24 12:17		0.00	0.80	20.20	0.00	0.00					Dry, sunny, mild			
			03/12/24 12:18		0.00	1.50	20.10	0.00	0.00					Dry, sunny, mild			
			03/12/24 12:19		0.00	1.60	20.20	0.00	0.00					Dry, sunny, mild			
			03/12/24 12:20		0.00	1.60	20.20	0.00	0.00					Dry, sunny, mild			
			03/12/24 12:21		0.00	1.60	20.10	0.00	0.00					Dry, sunny, mild			
			10/12/24 12:38	1027	0.00	2.00	18.40	0.00	0.00	0.00	0.00	0.68		Dry, sunny, cold			
			10/12/24 12:39		0.00	0.70	20.00	0.00	0.00					Dry, sunny, cold			
			10/12/24 12:40		0.00	0.40	20.40	0.00	0.00					Dry, sunny, cold			
			10/12/24 12:41		0.00	0.30	20.50	0.00	0.00					Dry, sunny, cold			
			10/12/24 12:42		0.00	0.30	20.60	0.00	0.00					Dry, sunny, cold			
		10/12/24 12:43		0.00	0.40	20.00	0.00	0.00					Dry, sunny, cold				
WS03			21/11/24 13:00	982	0.00	6.00	16.80	0.00	0.00	0.00	0.00	0.16		Dry, hazy, cool			
			21/11/24 13:01		0.00	0.70	19.60	0.00	0.00					Dry, hazy, cool			
			21/11/24 13:02											Test stopped due to ingress			
														of water			
			03/12/24 12:30	1006	0.00	0.40	20.10	0.00	0.00	0.00	0.00	GL		Dry, sunny, mild			
			03/12/24 12:31											Test stopped due to water			
														ingress			
		10/12/24 12:03	1027	0.00	2.00	17.70	0.00	0.00	0.00	0.00	GL		Dry, sunny, cold				
		10/12/24 12:04											Test stopped due to water				
													ingress				
WS04			21/11/24 13:16	982	0.00	0.60	18.90	0.00	1.00	0.00	0.00	0.81		Dry, hazy, cool			
			21/11/24 13:17		0.00	0.60	20.10	0.00	0.00					Dry, hazy, cool			
			21/11/24 13:18		0.00	0.50	20.30	0.00	0.00					Dry, hazy, cool			
			21/11/24 13:19		0.00	0.50	20.50	0.00	1.00					Dry, hazy, cool			
			21/11/24 13:20		0.00	0.40	20.50	0.00	1.00					Dry, hazy, cool			
			21/11/24 13:21		0.00	0.30	20.50	0.00	0.00					Dry, hazy, cool			
			03/12/24 12:51	1006	0.00	0.00	19.60	0.00	0.00	0.00	0.00	0.65		Dry, sunny, mild			
			03/12/24 12:52		0.00	0.40	19.80	0.00	0.00					Dry, sunny, mild			
			03/12/24 12:53		0.00	0.60	20.00	0.00	0.00					Dry, sunny, mild			
Originator		Title: RESULTS OF GAS AND WATER LEVEL MONITORING IN STANDPIPES												<div></div>		Fig No:	
JMcM																B103	
Chk & App	Status															Sheet 2 of 3	
CJH		Final															




Site: CAMBUSHINNIE 400KV SUBSTATION

Contract No: 26762

Client: Balfour Beatty

Engineer: Balfour Beatty

* Water level measurements taken from ground level.

Borehole No.	Surveyed Level (m OD)	Depth to Base of Standpipe (m)	Date /Time	Atmospheric Pressure (mBar)	Gas Composition					Differential Pressure (Pa)	Flow (l/hr)	Depth to Water (m) (mBGL)	Depth (mAOD)	Remarks
					CH ₄ (%vol)	CO ₂ (%vol)	O ₂ (%vol)	H ₂ S (ppm)	CO (ppm)					
WS04			03/12/24 12:54		0.00	0.70	20.10	0.00	0.00					Dry, sunny, mild
			03/12/24 12:55		0.00	0.70	20.10	0.00	0.00					Dry, sunny, mild
			03/12/24 12:56		0.00	0.80	20.20	0.00	1.00					Dry, sunny, mild
			10/12/24 13:47	1027	0.00	0.30	19.60	0.00	0.00	0.00	0.00	0.59		Dry, sunny, cold
			10/12/24 13:48		0.00	0.50	19.90	0.00	0.00					Dry, sunny, cold
			10/12/24 13:49		0.00	0.50	19.90	0.00	0.00					Dry, sunny, cold
			10/12/24 13:50		0.00	0.50	19.90	0.00	0.00					Dry, sunny, cold
			10/12/24 13:51		0.00	0.50	20.00	0.00	0.00					Dry, sunny, cold
WS06			10/12/24 13:52		0.00	0.40	20.00	0.00	0.00					Dry, sunny, cold
			21/11/24 13:34	980	0.00	0.00	19.90	0.00	0.00	0.00	0.00	0.53		Dry, sunny, cool
			21/11/24 13:35		0.00	0.50	20.50	0.00	0.00					Dry, sunny, cool
			21/11/24 13:36		0.00	0.40	20.60	0.00	0.00					Dry, sunny, cool
			21/11/24 13:37		0.00	0.30	20.70	0.00	0.00					Dry, sunny, cool
			21/11/24 13:38		0.00	0.20	20.70	0.00	0.00					Dry, sunny, cool
			21/11/24 13:39		0.00	0.10	20.70	0.00	1.00					Dry, sunny, cool
			03/12/24 14:35	1005	0.00	0.80	18.90	0.00	0.00	0.00	0.00	0.23		Dry, sunny, mild
			03/12/24 14:36		0.00	0.70	20.00	0.00	0.00					Dry, sunny, mild
			03/12/24 14:37		0.00	0.70	20.20	0.00	0.00					Dry, sunny, mild
			03/12/24 14:38		0.00	0.60	20.40	0.00	0.00					Dry, sunny, mild
			03/12/24 14:39		0.00	0.50	20.40	0.00	0.00					Dry, sunny, mild
			03/12/24 14:40		0.00	0.50	20.40	0.00	0.00					Dry, sunny, mild
			10/12/24 14:30	1024	0.00	0.40	19.70	0.00	0.00	0.00	0.00	0.25		Dry, sunny, cold
			10/12/24 14:31		0.00	0.00	20.60	0.00	0.00					Dry, sunny, cold
			10/12/24 14:32		0.00	0.00	20.70	0.00	1.00					Dry, sunny, cold
			10/12/24 14:33		0.00	0.00	20.70	0.00	0.00					Dry, sunny, cold
			10/12/24 14:34											Test stopped due to water ingress
			21/11/24 13:51	979	0.00	0.00	20.30	0.00	0.00	0.00	0.00	0.61		Dry, sunny, cool
			21/11/24 13:52		0.00	0.00	20.60	0.00	0.00					Dry, sunny, cool
			21/11/24 13:53		0.00	0.00	20.60	0.00	0.00					Dry, sunny, cool
			21/11/24 13:54		0.00	0.00	20.60	0.00	0.00					Dry, sunny, cool
			21/11/24 13:55		0.00	0.00	20.70	0.00	0.00					Dry, sunny, cool
			21/11/24 13:56		0.00	0.00	20.60	0.00	0.00					Dry, sunny, cool
			03/12/24 14:18	1005	0.00	3.60	17.60	0.00	0.00	0.00	0.00	0.45		Dry, sunny, mild
			03/12/24 14:19		0.00	2.30	16.60	0.00	0.00					Dry, sunny, mild
			03/12/24 14:20		0.00	2.30	17.00	0.00	0.00					Dry, sunny, mild
			03/12/24 14:21		0.00	2.30	17.10	0.00	0.00					Dry, sunny, mild
			03/12/24 14:22		0.00	2.30	17.30	0.00	0.00					Dry, sunny, mild
			03/12/24 14:23		0.00	2.00	17.50	0.00	0.00					Dry, sunny, mild
			10/12/24 15:19	1024	0.00	0.00	20.00	0.00	0.00	0.00	0.00	0.42		Dry, sunny, cold
			10/12/24 15:20		0.00	3.30	17.90	0.00	0.00					Dry, sunny, cold
			10/12/24 15:21											Test stopped due to water ingress
														ingress
	Originator	Title:												Fig No:
	JMcM	RESULTS OF GAS AND WATER LEVEL MONITORING IN STANDPIPES												B103
Chk & App	Status													Sheet 3 of 3
CJH	Final													



Site: CAMBUSHINNIE 400KV SUBSTATION

Contract No: 26762

Client: Balfour Beatty

Engineer: Balfour Beatty

Style: APPENDIX C File: P:\GINTWPROJECTS\26762.GPJ Printed: 12/12/2024 16:46:52 Raeburn Drilling and Geotechnical Whistleberry Rd, Hamilton ML3 0HP Tel: 01698-711177 E-mail: enquiries@raeburndrilling.com

APPENDIX C
GEOTECHNICAL LABORATORY TESTING





Site: CAMBUSHINNIE 400KV SUBSTATION

Contract No: 26762

Client: Balfour Beatty

Engineer: Balfour Beatty

TEST**STANDARD****CLASSIFICATION TESTS**

Determination of water content
Determination of liquid limit
Determination of liquid and plastic limits
Determination of bulk density
Determination of particle density
Determination of particle size distribution

BS EN ISO 17892-1:2014
BS 1377 : 1990 : Part 2 : 4.3 and 4.4
BS EN ISO 17892-12:2018
BS EN ISO 17892-2:2014
BS EN ISO 17892-3:2016
BS EN ISO 17892-4:2016

CHEMICAL TESTS

Determination of organic matter content
Determination of mass loss on ignition
Determination of sulphate content of soil and groundwater
Determination of chloride content
Determination of pH value

BS 1377 : 1990 : Part 3 : 3.4
BS 1377 : 1990 : Part 3 : 4.3
BS 1377 : 1990 : Part 3 : 5.2, 5.3 and 5.5
BS 1377 : 1990 : Part 3 : 7.2 and 7.3
BS 1377 : 1990 : Part 3 : 9.5

COMPACTION-RELATED TESTS

Determination of dry density/moisture content relationship
Determination of moisture condition value (MCV)
Determination of California Bearing Ratio (CBR)

BS 1377 : 1990 : Part 4 : 3.3 to 3.6
SDD Tech Memo SH7/83; SDD Appls Guide No.1 Rev. 1989
BS 1377 : 1990 : Part 4 : 7.4

CONSOLIDATION AND STRENGTH TESTS

Incremental loading oedometer test
Unconfined compression test
Unconsolidated undrained triaxial test
Consolidated triaxial compression tests on water saturated soils
Lab Vane Tests
Direct shear tests
Permeability tests
Fall cone test

BS EN ISO 17892-5:2017
BS EN ISO 17892-7:2018
BS EN ISO 17892-8:2018
BS EN ISO 17892-9:2018
BS 1377 : 1990
BS EN ISO 17892-10:2019
BS EN ISO 17892-11:2019
BS EN ISO 17892-6:2017

ROCK TESTS

Determination of point load strength
Determination of unconfined compressive strength
LA Abrasion Tests
Magnesium Soundness Tests
Slake durability
Rock porosity / density

ISRM Commission on Testing Methods, 1985
ASTM D7012-14
BS EN 1097-2:2010 and BS 818 : Part 2 : 1990
BS EN 1367-2
ISRM Suggested methods
ISRM Suggested methods



Raeburn Drilling & Geotechnical Ltd t/a igne H

Whistleberry Road

Hamilton

ML6 OHP


For the attention of Ramsay Bell

Report No: A15413-1

Issue No: 01

Date of issue: 26/11/2024



LABORATORY TEST REPORT




Project Name		CAMBUSHINNIE HAUL ROAD	
Project Number		A15413-1	Date samples received
Your Ref		26762	Date written instructions received 07/11/2024
Purchase Order		26762	Date testing commenced 11/11/2024
Please find enclosed the results as summarised below			
Figure / Table	Test Quantity	Description	ISO 17025 Accredited
	54	Determination of Water Content	Yes
	11	Atterberg Limit	Yes
	37	Particle Size Distribution	Yes
	4	Moisture Content / Dry Density Relationship	Yes
	5	California Bearing Ratio	Yes
	4	Unconsolidated Undrained Single Stage Triaxial Compression	Yes
	2	Point Load Index	Yes
Remarks: Interim results. Oedometer & Chemistry to follow			Key to symbols used in this report S/C : Testing was sub-contracted
Issued by: C Donnelly		 26/11/2024 Laboratory Coordinator	
Approved Signatories: C Donnelly - Laboratory Coordinator, C Loudon - Field Services Manager, S McDonagh - Laboratory Supervisor, S Gilchrist - Quality Supervisor, R Hobson - Field Services Manager, T Johnson - Senior Technician			
<p>Unless we are notified to the contrary, any remaining samples will be disposed of, 4 weeks after the date this report was issued</p> <p>Results contained in this report are provisional unless signed by an approved signatory</p> <p>This report should not be reproduced without written approval from Terra Tek Limited (Trading as igne)</p> <p>The enclosed results remain the property of Terra Tek Limited (Trading as igne) and we reserve the right to withdraw</p> <p>Only those results indicated in this report are UKAS accredited and any opinions or interpretations expressed are outside the scope of UKAS accreditation.</p> <p>Feedback on this report may be left:</p> <p>https://forms.office.com/pages/responsepage.aspx?id=CwCZTjwYeUGWZfDBJbk1g0fy8UwdJQhLtt3HBD1SytUMzNYWTdFVpMWjdHREcwQUq1MDJLM09OTi4u&wdLOR</p>			





62 Rochsolloch Road, Airdrie, ML6 9BG
Tel: +44 (0)1236 747 949 Fax: +44 (0)1236 747 849
airdrie@igne.com
www.igne.com

Terra Tek Ltd is registered in Scotland. SC121594
Offices in Airdrie, Aston Clinton, Barnsley, Daventry

Head Office: Whistleberry Road, Hamilton, Glasgow, Scotland, ML3 0HP

				Site CAMBUSHINNIE HAUL ROAD		Contract No 26762	
				Client Balfour Beatty			
				Engineer WSP			
Sample Identification				Lab Sample ID	Non Engineering Description	Water Content %	
Exploratory Hole	Depth m	Sample Ref	Sample Type				
BH01	0.80		B	2030056	Brown silty sandy fine to coarse GRAVEL with cobbles	13	
BH01	1.20		B	2030057	Brown silty SAND and GRAVEL. Gravel is fine to coarse	16	
BH01	11.70		UT	2030061	Brown gravelly very silty SAND. Gravel is fine to coarse	24.6	
BH01	14.70		UT	2030062	Brown gravelly very silty SAND. Gravel is fine to coarse	22.8	
BH01	5.70		UT	2030059	Brown gravelly very silty SAND. Gravel is fine to coarse	23.6	
BH01	8.70		UT	2030060	Brown gravelly very silty SAND. Gravel is fine to coarse	22.6	
BH02	0.80		B	2030065	Brown slightly silty sandy fine to coarse GRAVEL with cobbles	6.6	
BH02	1.20		D	2030066	Brown silty very sandy fine to coarse GRAVEL with cobbles	7.3	
BH02	7.20		D	2030067	Brown slightly sandy SILT	34	
TP01	2.20		D	2030072	Brown slightly silty sandy fine to coarse GRAVEL	10.1	
TP02	1.50		D	2030073	Brown silty sandy fine to coarse GRAVEL	9	
TP03	1.50		D	2030076	Brown silty sandy fine to coarse GRAVEL	9.6	
TP03	2.00		LB	2030075	Brown slightly silty sandy fine to coarse GRAVEL with cobbles	7.9	
TP04	0.50		D	2030077	Brown gravelly very silty SAND. Gravel is fine to coarse	20.5	
Notes							
Originator		Checked & Approved		Determination of the Water Content BS EN ISO 17892-1:2014		 Figure C1 Sheet 1 of 4	
AM		CD 26/11/2024					

				Site CAMBUSHINNIE HAUL ROAD		Contract No 26762	
				Client Balfour Beatty			
				Engineer WSP			
Sample Identification				Lab Sample ID	Non Engineering Description	Water Content %	
Exploratory Hole	Depth m	Sample Ref	Sample Type				
TP04	2.50		D	2030078	Brown silty very sandy fine to coarse GRAVEL	9.8	
TP05	2.60		D	2030081	Brown slightly silty sandy fine to coarse GRAVEL	8.8	
TP06	1.50		D	2030083	Brown silty very gravelly SAND. Gravel is fine to coarse	17.5	
TP07	2.50		D	2030084	Brown silty very sandy fine to coarse GRAVEL	12.2	
TP08	1.20		D	2030086	Brown silty very sany fine to coarse GRAVEL	18.6	
TP09	2.20		D	2030088	Brown slightly silty sandy fine to coarse GRAVEL	17.6	
TP10	1.50		D	2030089	Brown silty sandy fine to coarse GRAVEL	14.3	
TP12	1.20		D	2030092	Brown silty very gravelly SAND . Gravel is fine to coarse	10.9	
TP12	2.20		D	2030093	Brown silty gravelly SAND . Gravel is fine to coarse	10.9	
TP13	1.50		LB	2030095	Brown silty SAND and GRAVEL. Gravel is fine to coarse	15	
TP13	2.50		LB	2030096	Brown silty SAND and GRAVEL with cobbles. Gravel is fine to coarse	13.3	
TP14	0.50		LB	2030100	Brown silty very sandy fine to coarse GRAVEL. Gravel is fine to coarse	16	
TP14	2.50		LB	2030101	Brown silty SAND and GRAVEL. Gravel is fine to coarse	15.9	
TP15	0.50		D	2030103	Brown silty gravelly SAND . Gravel is fine to coarse	20.7	
Notes							
Originator		Checked & Approved		Determination of the Water Content BS EN ISO 17892-1:2014		 Figure C2 Sheet 2 of 4	
AM		 26/11/2024					

<div></div>				SiteCAMBUSHINNIE HAUL ROAD		Contract No26762	
				ClientBalfour Beatty			
				EngineerWSP			
Sample Identification				Lab Sample ID	Non Engineering Description	Water Content %	
Exploratory Hole	Depth m	Sample Ref	Sample Type				
TP15	1.50		D	2030104	Brown silty gravelly SAND . Gravel is fine to coarse	20.6	
TP16	1.00		LB	2030105	Brown silty gravelly SAND . Gravel is fine to coarse	21.8	
TP17	0.50		D	2030108	Brown silty very sandy fine to coarse GRAVEL	18.1	
TP18	2.50		D	2030110	Brown silty SAND and GRAVEL. Gravel is fine to coarse	17.8	
TP19	1.50		D	2030113	Brown silty SAND and GRAVEL. Gravel is fine to coarse	11.3	
TP20	1.20		D	2030115	Brown silty gravelly SAND . Gravel is fine to coarse	15.2	
TP21	1.00		D	2030117	Brown silty gravelly SAND . Gravel is fine to coarse	18.2	
TP21	3.00		D	2030118	Brown silty gravelly SAND . Gravel is fine to coarse	15.9	
WS01	0.50		D	2030122	Brown gravelly silty SAND. Gravel is fine to coarse	21.1	
WS01	1.00		D	2030123	Brown gravelly silty SAND. Gravel is fine to coarse	21	
WS01	1.20		UL	2030120	Brown silty very sandy fine to coarse GRAVEL	13.8	
WS01	2.00		D	2030124	Brown silty very sandy fine to coarse GRAVEL	10.2	
WS01	4.20		D	2030125	Brown gravelly silty SAND. Gravel is fine to coarse	19.1	
WS02	1.20		D	2030130	Brown silty SAND and GRAVEL. Gravel is fine to coarse	13.1	
Notes							
Originator	Checked & Approved		Determination of the Water Content BS EN ISO 17892-1:2014			<div>Figure C3</div>	
AM	<div>26/11/2024</div>						
						Sheet 3 of 4	

Version 026 - 01/09/2023
1212 - Moisture Content Table - A15413-1.xls

62 Rochsolloch Road, Airdrie, ML6 9BG
Lab Project No A15413-1 : 26/11/2024 12:06:33

<div><div><div></div><div>igne</div></div></div>				Site CAMBUSHINNIE HAUL ROAD		Contract No 26762	
				Client Balfour Beatty			
				Engineer WSP			
Sample Identification				Lab Sample ID	Non Engineering Description	Water Content %	
Exploratory Hole	Depth m	Sample Ref	Sample Type				
WS03	0.50		D				
WS03	2.20		B				
WS04	0.80		B				
WS04	2.20		D				
WS05	0.40		D				
WS05	2.20		D				
WS05	2.20		UL				
WS05	2.80		D				
WS06	2.20		D				
WS06	3.00		D				
WS07	1.20		D				
WS07	1.20		UL				
Notes							
Originator		Checked & Approved					
AM		CD 26/11/2024					



Site CAMBUSHINNIE HAUL ROAD

Client Balfour Beatty

Engineer WSP

Contract No. 26762

Hole ID BH01



Sample Ref

Depth (m) 5.70

Sample Type UT

Non Engineering Description : Brown gravelly very silty SAND. Gravel is fine to coarse

Preparation : Sample oven dried, Percentage retained on 425µm sieve measured by wet sieving



Sample was determined to be Non-Plastic after preparation

Liquid Limit was determined by mixing using increasing water content and 30° cone

Results :

As Received Water Content : (BS EN ISO 17892-1:2014)	23.6 %
Percentage retained on 425µm sieve :	23 %
Liquid Limit :	27 %
Plastic Limit :	Non-Plastic %

Equivalent water content of material passing 425µm sieve : 30.6 %

Originator

Checked & Approved

CM

CD
26/11/2024

**Liquid Limit (Four Point Cone Penetrometer Method)
Plastic Limit, Plasticity Index & Liquidity Index**

BS EN ISO 17892-12:2018 Clause 5.3

BS EN ISO 17892-12:2018 Clause 5.5



Figure C5

Sheet 1 of 1



Site CAMBUSHINNIE HAUL ROAD

Client Balfour Beatty

Engineer WSP

Contract No. 26762

Hole ID BH01



Sample Ref

Depth (m) 8.70

Sample Type UT

Non Engineering Description : Brown gravelly very silty SAND. Gravel is fine to coarse

Preparation : Sample oven dried, Percentage retained on 425µm sieve measured by wet sieving



Sample was determined to be Non-Plastic after preparation

Liquid Limit was determined by mixing using increasing water content and 30° cone

Results :

As Received Water Content : (BS EN ISO 17892-1:2014) 22.6 %
 Percentage retained on 425µm sieve : 9 %
 Liquid Limit : 30 %
 Plastic Limit : Non-Plastic %

Equivalent water content of material passing 425µm sieve : 24.8 %



Originator	Checked & Approved	Liquid Limit (Four Point Cone Penetrometer Method) Plastic Limit, Plasticity Index & Liquidity Index BS EN ISO 17892-12:2018 Clause 5.3 BS EN ISO 17892-12:2018 Clause 5.5	Figure C6 Sheet 1 of 1
CM	CD 26/11/2024		



Site	CAMBUSHINNIE HAUL ROAD	Contract No.	26762
Client	Balfour Beatty	Hole ID	BH01
Engineer	WSP	Sample Ref	
		Depth (m)	11.70
		Sample Type	UT

Non Engineering Description : Brown gravelly very silty SAND. Gravel is fine to coarse

Preparation : Sample oven dried, Percentage retained on 425µm sieve measured by wet sieving



Sample was determined to be Non-Plastic after preparation
Liquid Limit was determined by mixing using increasing water content and 30° cone

Results :
As Received Water Content : (BS EN ISO 17892-1:2014) 24.6 %
Percentage retained on 425µm sieve : 9 %
Liquid Limit : 28 %
Plastic Limit : Non-Plastic %

Equivalent water content of material passing 425µm sieve : 27.0 %

Originator	Checked & Approved	Liquid Limit (Four Point Cone Penetrometer Method) Plastic Limit, Plasticity Index & Liquidity Index BS EN ISO 17892-12:2018 Clause 5.3 BS EN ISO 17892-12:2018 Clause 5.5	 Figure C7 Sheet 1 of 1
CM	CD 26/11/2024		



Site CAMBUSHINNIE HAUL ROAD

Client Balfour Beatty

Engineer WSP

Contract No. 26762

Hole ID BH01



Sample Ref

Depth (m) 14.70

Sample Type UT

Non Engineering Description : Brown gravelly very silty SAND. Gravel is fine to coarse

Preparation : Sample oven dried, Percentage retained on 425µm sieve measured by wet sieving



Sample was determined to be Non-Plastic after preparation

Liquid Limit was determined by mixing using increasing water content and 30° cone

Results :

As Received Water Content : (BS EN ISO 17892-1:2014) 22.8 %
 Percentage retained on 425µm sieve : 12 %
 Liquid Limit : 30 %
 Plastic Limit : Non-Plastic %

Equivalent water content of material passing 425µm sieve : 25.9 %

Originator	Checked & Approved	Liquid Limit (Four Point Cone Penetrometer Method) Plastic Limit, Plasticity Index & Liquidity Index BS EN ISO 17892-12:2018 Clause 5.3 BS EN ISO 17892-12:2018 Clause 5.5	Figure C8 Sheet 1 of 1
CM	CD 26/11/2024		



Site CAMBUSHINNIE HAUL ROAD

Client Balfour Beatty

Engineer WSP

Contract No. 26762

Hole ID BH02



Sample Ref

Depth (m) 7.20

Sample Type D

Non Engineering Description : Brown slightly sandy SILT

Preparation : Sample oven dried, Percentage retained on 425µm sieve measured by wet sieving



Sample was determined to be Non-Plastic after preparation

Liquid Limit was determined by mixing using increasing water content and 30° cone

Results :

As Received Water Content : (BS EN ISO 17892-1:2014) 34.0 %
 Percentage retained on 425µm sieve : 6 %
 Liquid Limit : 34 %
 Plastic Limit : Non-Plastic %

Equivalent water content of material passing 425µm sieve : 36.2 %

Originator	Checked & Approved	Liquid Limit (Four Point Cone Penetrometer Method) Plastic Limit, Plasticity Index & Liquidity Index BS EN ISO 17892-12:2018 Clause 5.3 BS EN ISO 17892-12:2018 Clause 5.5	Figure C9 Sheet 1 of 1
CM	CD 26/11/2024		



Site CAMBUSHINNIE HAUL ROAD

Client Balfour Beatty

Engineer WSP

Contract No. 26762

Hole ID WS03



Sample Ref

Depth (m) 0.50

Sample Type D

Non Engineering Description : Brown gravelly silty SAND. Gravel is fine to medium

Preparation : Sample oven dried, Percentage retained on 425µm sieve measured by wet sieving



Sample was determined to be Non-Plastic after preparation

Liquid Limit was determined by mixing using increasing water content and 30° cone

Results :

As Received Water Content : (BS EN ISO 17892-1:2014) 32.9 %
Percentage retained on 425µm sieve : 26 %
Liquid Limit : 37 %
Plastic Limit : Non-Plastic %

Equivalent water content of material passing 425µm sieve : 44.5 %



Originator	Checked & Approved	Liquid Limit (Four Point Cone Penetrometer Method) Plastic Limit, Plasticity Index & Liquidity Index BS EN ISO 17892-12:2018 Clause 5.3 BS EN ISO 17892-12:2018 Clause 5.5	Figure C10 Sheet 1 of 1
CM	CD 26/11/2024		



Site	CAMBUSHINNIE HAUL ROAD	Contract No.	26762
Client	Balfour Beatty	Hole ID	WS05
Engineer	WSP	Sample Ref	
		Depth (m)	2.20
		Sample Type	D

Non Engineering Description : Brown silty SAND and GRAVEL. Gravel is fine to coarse

Preparation : Sample oven dried, Percentage retained on 425µm sieve measured by wet sieving



Sample was determined to be Non-Plastic after preparation
Liquid Limit was determined by mixing using increasing water content and 30° cone

Results :

As Received Water Content : (BS EN ISO 17892-1:2014) 10.6 %
Percentage retained on 425µm sieve : 52 %
Liquid Limit : 25 %
Plastic Limit : Non-Plastic %

Equivalent water content of material passing 425µm sieve : 22.1 %

Originator	Checked & Approved	Liquid Limit (Four Point Cone Penetrometer Method) Plastic Limit, Plasticity Index & Liquidity Index BS EN ISO 17892-12:2018 Clause 5.3 BS EN ISO 17892-12:2018 Clause 5.5	Figure C11 Sheet 1 of 1
CM	CD 26/11/2024		



Site CAMBUSHINNIE HAUL ROAD

Client Balfour Beatty

Engineer WSP

Contract No. 26762

Hole ID WS05



Sample Ref

Depth (m) 2.80

Sample Type D

Non Engineering Description : Brown silty very sandy fine to coarse GRAVEL

Preparation : Sample oven dried, Percentage retained on 425µm sieve measured by wet sieving



Sample was determined to be Non-Plastic after preparation

Liquid Limit was determined by mixing using increasing water content and 30° cone

Results :

As Received Water Content : (BS EN ISO 17892-1:2014) 18.2 %
Percentage retained on 425µm sieve : 71 %
Liquid Limit : 31 %
Plastic Limit : Non-Plastic %

Equivalent water content of material passing 425µm sieve : 62.8 %



Originator	Checked & Approved	Liquid Limit (Four Point Cone Penetrometer Method) Plastic Limit, Plasticity Index & Liquidity Index BS EN ISO 17892-12:2018 Clause 5.3 BS EN ISO 17892-12:2018 Clause 5.5	Figure C12 Sheet 1 of 1
CM	CD 26/11/2024		



Site	CAMBUSHINNIE HAUL ROAD	Contract No.	26762
Client	Balfour Beatty	Hole ID	WS06
Engineer	WSP	Sample Ref	
		Depth (m)	2.20
		Sample Type	D

Non Engineering Description : Brown silty very sandy fine to coarse GRAVEL

Preparation : Sample oven dried, Percentage retained on 425µm sieve measured by wet sieving



Sample was determined to be Non-Plastic after preparation
Liquid Limit was determined by mixing using increasing water content and 30° cone

Results :

As Received Water Content : (BS EN ISO 17892-1:2014) 10.8 %
Percentage retained on 425µm sieve : 61 %
Liquid Limit : 27 %
Plastic Limit : Non-Plastic %

Equivalent water content of material passing 425µm sieve : 27.7 %

Originator	Checked & Approved	Liquid Limit (Four Point Cone Penetrometer Method) Plastic Limit, Plasticity Index & Liquidity Index BS EN ISO 17892-12:2018 Clause 5.3 BS EN ISO 17892-12:2018 Clause 5.5	Figure C13 Sheet 1 of 1
CM	CD 26/11/2024		