

TRANSMISSION

VOLUME 4: APPENDIX V5-7.3: SCHEDULE OF WATERCOURSE CROSSINGS – ALTERNATIVE ALIGNMENT



₩SLR

Strathy South Wind Farm Grid Connection

Appendix V5-7.3: Schedule of Watercourse Crossings – Alternative Alignment

ASH design+assessment

Prepared by:

SLR Consulting Limited

No. 50 Stirling Business Centre, Wellgreen, Stirling, FK8 2DZ

SLR Project No.: 428.013137.00001_0004

5 February 2025

Revision: Final

Making Sustainability Happen

Revision Record

Revision	Date	Prepared By	Checked By	Authorised By
Final	5 February 2025	A. Searle	K. Rainford	G. Robb
	Click to enter a date.			
	Click to enter a date.			
	Click to enter a date.			
	Click to enter a date.			

Basis of Report

This document has been prepared by SLR Consulting Limited (SLR) with reasonable skill, care and diligence, and taking account of the timescales and resources devoted to it by agreement with ASH design+assessment (the Client) as part or all of the services it has been appointed by the Client to carry out. It is subject to the terms and conditions of that appointment.

SLR shall not be liable for the use of or reliance on any information, advice, recommendations and opinions in this document for any purpose by any person other than the Client. Reliance may be granted to a third party only in the event that SLR and the third party have executed a reliance agreement or collateral warranty.

Information reported herein may be based on the interpretation of public domain data collected by SLR, and/or information supplied by the Client and/or its other advisors and associates. These data have been accepted in good faith as being accurate and valid.

The copyright and intellectual property in all drawings, reports, specifications, bills of quantities, calculations and other information set out in this report remain vested in SLR unless the terms of appointment state otherwise.

This document may contain information of a specialised and/or highly technical nature and the Client is advised to seek clarification on any elements which may be unclear to it.

Information, advice, recommendations and opinions in this document should only be relied upon in the context of the whole document and any documents referenced explicitly herein and should then only be used within the context of the appointment.

Table of Contents

Basi	Basis of Reporti		
1.0	Introduction1		
1.1	Relevant Legislation1		
2.0	Watercourse Crossing Details2		

1.0 Introduction

This Appendix contains information relating to the proposed permanent and temporary watercourse crossings and existing watercourse crossings on tracks which are scheduled to be upgraded to enable construction of the Proposed Development with the Alternative Alignment.

Where access was possible, this report presents photographs and dimensions for each proposed crossing point. The final design of each crossing solution would be agreed with Scottish Environment Protection Agency (SEPA) prior to construction and be determined as part of the detailed site design.

The survey of the watercourse crossings was undertaken between April and September 2024 by experienced SLR hydrologists.

The location of the watercourse crossings is shown in Volume 2: Figure V5-7.1.

1.1 Relevant Legislation

The Water Framework Directive (2000/60/EC) (WFD) has been transposed into Scottish legislation as the Water Environment and Water Services (Scotland) Act 2003¹ (or WEWS) and has given Scottish ministers powers to introduce regulatory controls over activities in order to protect and improve Scotland's water environment. The water environment includes wetlands, rivers, lochs, transitional waters (estuaries), coastal waters and groundwater. These regulatory controls, known as the Water Environment (Controlled Activities) (Scotland) Regulations 2011² (CAR) came into force in 2011 and have since been amended in 2013, 2017, and 2021.

With respect to watercourse crossings, CAR requires that all engineering works in inland surface waters and wetlands are subject to authorisation and allow for proportionate risk-based regulation which is outlined in the CAR Practical Guide³. SEPA provide authorisation for watercourse crossings shown on the 1:50,000 scale Ordnance Survey (OS) maps (Landranger Series). All other watercourses are classed as "minor watercourse" and are exempt under CAR.

The design, construction and/or improvements to the crossings would be agreed with SEPA prior to any construction works commencing in accordance with CAR as part of the detailed development design.

³ SEPA (July 2024) The Water Environment (Controlled Activities) (Scotland) Regulations 2011. A Practical Guide v9.4, available at <u>car-a-practical-guide.docx</u> [Accessed December 2024]



¹ Water Environment and Water Services (Scotland) Act 2003, available at https://www.legislation.gov.uk/asp/2003/3/contents [Accessed June 2024]

² Water Environment (Controlled Activities) (Scotland) Regulations 2011, available at https://www.legislation.gov.uk/ssi/2011/209/contents/made [Accessed June 2024]

2.0 Watercourse Crossing Details

Watercourse Crossing ID	WX01
Watercourse Crossing Details	NGR: NC 84360 62465
	Status: New Temporary Crossing
	Watercourse Width: N/A
	Watercourse Depth: N/A
	Notes : No active watercourse recorded during survey. Evidence of peat excavation noted upstream of watercourse.
Photograph Looking Upstream	N/A
Photograph Looking Downstream	N/A

Watercourse Crossing ID	WX02
Watercourse Crossing Details	NGR: NC 84827 62805 Status: New Permanent Crossing Watercourse Width: N/A Watercourse Depth: N/A Notes: Boggy ground with no obvious flowing water. This area is located in a channel which is up to 2 m wide and 1.5 m deep and incised in peat.
Photograph Looking Upstream	
Photograph Looking Downstream	

Watercourse Crossing ID	WX03
Watercourse Crossing	NGR: NC 85514 64336
Details	Status: Existing Crossing
	Crossing Type: Arch box culvert
	Crossing Dimensions: 0.5 m wide and 1 m tall
	Watercourse Width: 0.5 to 1 m
	Watercourse Depth: 0.2 m
	Notes: Watercourse incised in peat.
Photograph Looking Upstream	
Photograph Looking at Culvert Exit from Downstream	

Watercourse Crossing ID	WX04
Watercourse Crossing	NGR: NC 86486 64399
Details	Status: Existing Crossing
	Watercourse Width: 0.4 m
	Watercourse Depth: 0.3 m
	Notes : Unable to access existing culvert due to vegetation cover.
Photograph Looking Upstream	
Photograph Looking Downstream	

Watercourse Crossing ID	WX05
Watercourse Crossing Details	NGR: NC 86522 64636 Status: New Permanent Crossing Watercourse Width: 0.4 m Watercourse Depth: 0.2 m Notes: Watercourse surveyed approximately 70 m downstream of the proposed crossing point. Watercourse located in a slightly deeper channel approximately 0.5 m deep.
Photograph Looking Upstream	decper enamer approximately 0.0 m decp.
Photograph Looking Downstream	

Watercourse Crossing ID	WX06
Watercourse Crossing Details	NGR: NC 86706 64821 Status: Existing Crossing Watercourse Width: N/A Watercourse Depth: N/A Notes: No watercourse or existing culvert recorded during survey. Potential buried drain / culvert.
Photograph Looking Upstream	
Photograph Looking Downstream	

Watercourse Crossing ID	WX07
Watercourse Crossing Details	NGR: NC 86756 64824 Status: New Permanent Crossing Watercourse Width: N/A
	Watercourse Depth: N/A Notes: No watercourse recorded during survey. Potential buried drain or culvert.
Photograph Looking Upstream	N/A
Photograph Looking Downstream	N/A

Watercourse Crossing ID	WX08
Watercourse Crossing Details	NGR: NC 87150 64860 Status: New Permanent Crossing Watercourse Width: N/A Watercourse Depth: N/A Notes: No watercourse recorded during survey. Change in vegetation is noted to be approximately 1 m wide. Potential buried drain or culvert.
Photograph Looking Upstream	
Photograph Looking Downstream	

Watercourse Crossing ID	WX09
Watercourse Crossing	NGR: NC 87674 63527
Details	Status: New Permanent Crossing
	Watercourse Width: N/A
	Watercourse Depth: N/A
	Notes: No active watercourse noted during survey, however, a
	waterlogged area up to 4m wide and 0.5m deep was witnessed.
Photograph Looking Upstream	
Photograph Looking Downstream	and the second se
Downstream	
	and the second sec
	Lind and the second sec
	and the second of the second sec

Watercourse Crossing ID	WX10
Watercourse Crossing Details	NGR: NC 88804 61979 Status: Existing Crossing Watercourse Width: N/A Watercourse Depth: N/A Notes: Waterlogged area with no active watercourse or flowing water. In a wider channel which is 1.5m wide and 1m deep downstream of crossing. No formal drainage features (culvert etc) noted.
Photograph Looking Upstream	
Photograph Looking Downstream	

Watercourse Crossing ID	WX11
Watercourse Crossing	NGR: NC 88959 62083
Details	Status: Existing Crossing
	Crossing Type: N/A
	Crossing Dimensions: N/A
	Watercourse Width: N/A
	Watercourse Depth: N/A
	Notes : Downstream of WX10. Crossing location inaccessible during survey. Watercourse adjacent to track (downstream of proposed crossing point) is approximately 1.2 m wide and 0.2 m deep.
Photograph Looking Upstream	Not surveyed.
Photograph Looking Downstream	Not surveyed.

Watercourse Crossing ID	WX12
Watercourse Crossing Details	NGR: NC 88514 61534 Status: New Permanent Crossing Watercourse Width: N/A Watercourse Depth: N/A Notes: No active watercourse. Channel extends to 0.4m wide and 0.5m deep. Small footbridge noted immediately downstream of crossing point with a 0.2m diameter corrugated metal circular pipe beneath.
Photograph Looking Upstream	
Photograph Looking Downstream	

Watercourse Crossing ID	WX13
Watercourse Crossing Details	NGR: NC 88753 61422 Status: Existing Crossing Crossing Type: Corrugated metal circular culvert. Crossing Dimensions: 0.5 m diameter. Watercourse Width: N/A Watercourse Depth: N/A Notes: No active watercourse recorded during survey. Culvert entrance and exit is heavily vegetated. Culvert is reinforced with stone headwall.
Photograph Looking Upstream	
Photograph Looking Downstream	



Watercourse Crossing ID	WX14
Watercourse Crossing Details	NGR: NC 88722 61385 Status: Existing Crossing Watercourse Width: 0.5m Watercourse Depth: 0.2m Notes: Watercourse is located in a channel which is up to 2 m wide downstream of crossing point. No obvious watercourse upstream of the crossing point. No evidence of existing drainage at crossing location (culvert etc), however crossing point and upstream of crossing was overgrown during survey.
Photograph Looking Upstream	
Photograph Looking at Crossing from Downstream	

Watercourse Crossing ID	WX15
Watercourse Crossing Details	NGR: NC 88662 61252 Status: Existing Crossing Crossing Type: Corrugated metal circular culvert. Crossing Dimensions: 1.7 m diameter. Watercourse Width: 1.4 m Watercourse Depth: 0.3 m Notes: Channel upstream of culvert was overgrown. Culvert reinforced with stone headwall.
Photograph Looking at Culvert Entrance from Upstream	
Photograph Looking at Culvert Exit from Downstream	

Watercourse Crossing ID	WX16
Watercourse Crossing	NGR: NC 88603 61124
Details	Status: Existing Crossing
	Crossing Type: Twin circular culvert.
	Crossing Dimensions: 0.8 m diameter.
	Watercourse Width: 0.1 m
	Watercourse Depth: 0.2 m
	Notes: Watercourse located in a channel which is up to 2 m wide. Culverts reinforced with a stone headwall.
Photograph Looking at Culvert Entrance from Upstream	
Photograph Looking Downstream	



Watercourse Crossing ID	WX17
Watercourse Crossing Details	NGR: NC 88464 60965 Status: Existing Crossing Crossing Type: Corrugated circular culvert. Crossing Dimensions: 1 m diameter. Watercourse Width: 1.5 m Watercourse Depth: 0.3 m Notes: None.
Photograph Looking at Culvert Entrance from Upstream	
Photograph Looking at Culvert Exit from Downstream	

Watercourse Crossing	WX18
ID	
Watercourse Crossing	NGR: NC 8845 760867
Details	Status: Existing Crossing
	Crossing Type: Ford
	Watercourse Width: 2 m
	Watercourse Depth: 0.4 m
	Notes: Watercourse increases to approximately 6 m wide at crossing. Ford crossing is same width of existing track (approximately 3 m).
Photograph Looking at Crossing from Upstream	
Photograph Looking at Crossing from Downstream	

Watercourse Crossing ID	WX19
Watercourse Crossing Details	NGR: NC 88485 60719 Status: Existing Crossing Crossing Type: Corrugated circular culvert. Crossing Dimensions: 1.5 m diameter. Watercourse Width: 2 m Watercourse Depth: 0.4 m Notes: Watercourse slightly larger downstream of crossing compared to upstream and located in a channel which is up to 3 m wide and 1.5m deep.
Photograph Looking at Culvert Entrance from Upstream	<image/>
Photograph Looking Downstream	

Watercourse Crossing ID	WX20
Watercourse Crossing Details	NGR: NC 89116 61280 Status: Existing Crossing Crossing Type: Wooden bridge Crossing Dimensions: 1.5 m span Watercourse Width: 1 m to 1.5 m Watercourse Depth: 0.3 m to 0.4 m Notes: At time of survey watercourse had a very slow flow and is located in a channel which is up to 2 m wide and 1.5 m deep.
Photograph Looking Upstream	
Photograph Looking Downstream	

Watercourse Crossing ID	WX21
Watercourse Crossing	NGR: NC 89146 61257
Details	Status: Existing Crossing
	Crossing Type: Wooden bridge
	Crossing Dimensions: 2 m span
	Watercourse Width: 1.5 m to 3 m
	Watercourse Depth: 0.3 m to 0.4 m
	Notes : Watercourse has a rocky bed and is located in a channel which is up to 3 m wide and 1 m deep.
Photograph Looking at Crossing	
Photograph Looking Downstream	

Watercourse Crossing ID	WX22
Watercourse Crossing Details	NGR: NC 89152 61008 Status: Existing Crossing Crossing Type: Corrugated pipe. Crossing Dimensions: 0.4m diameter. Watercourse Width: N/A Watercourse Depth: N/A Notes: Watercourse recorded as dry during survey. Watercourse located in channel which is 1m deep and 0.8m wide.
Photograph Looking at Culvert Entrance from Upstream	<image/>
Photograph Looking Downstream	


Watercourse Crossing ID	WX23
Watercourse Crossing Details	NGR: NC 89277 60691 Status: Existing Crossing Watercourse Width: N/A Watercourse Depth: N/A Notes: Channel very overgrown. Watercourse and existing culvert was inaccessible during the survey. Watercourse located in a channel which is approximately 2m wide and 1.5m deep.
Photograph Looking Upstream	
Photograph Looking Downstream	

Watercourse Crossing ID	WX24
Watercourse Crossing Details	NGR: NC 89384 60262 Status: Existing Crossing Crossing Type: Ford (dry during survey). Watercourse Width: N/A Watercourse Depth: N/A Notes: Standing water noted upstream, but no flowing / active watercourse recorded during the survey. Watercourse located in a channel which is up to 1m wide and 0.3m deep.
Photograph Looking at Crossing	
Photograph Looking Downstream	<image/>

Watercourse Crossing ID	WX25
Watercourse Crossing Details	NGR: NC 89466 60054 Status: Existing Crossing Crossing Type: Ford Watercourse Width: 0.2 m Watercourse Depth: 0.1 m Notes: Watercourse located in a channel which up to 2 m wide and 0.5 m deep. Channel is slightly narrower upstream of crossing point. Downstream of crossing point watercourse channel ill-defined.
Photograph Looking at Crossing	<image/>
Photograph Looking Downstream	

Watercourse Crossing ID	WX26
Watercourse Crossing Details	NGR: NC 90490 59622
	Status: New UGC Crossing
	Watercourse Width: 1 m
	Watercourse Depth: 0.5 m
	Notes: Watercourse surveyed approximately 50m downstream of the proposed UGC crossing. Watercourse incised in bedrock and located within a channel which is up to 15m wide and 5m deep.
Photograph Looking Upstream	N/A
Photograph Looking Downstream	N/A

Watercourse Crossing ID	WX27
Watercourse Crossing Details	NGR: NC 90509 59699
	Status: New UGC Crossing
	Watercourse Width: 1 m
	Watercourse Depth: 0.5 m
	Notes : Noted to be a man-made channel. Watercourse surveyed approximately 20m downstream of the proposed UGC cable crossing.
Photograph Looking Upstream	N/A
Photograph Looking Downstream	N/A



Making Sustainability Happen